

04-16-01

09/8076542 T #  
Express Mail Label No. EL623519943US

04/13/01

PCT-1399 (1-2000) U.S. DEPARTMENT OF COMMERCE PATENT AND TRADEMARK OFFICE		ATTORNEY'S DOCKET NUMBER 5077-000031 U.S. APPLICATION NO. (If known, see 37 CFR 1.5)
TRANSMITTAL LETTER TO THE UNITED STATES DESIGNATED/ELECTED OFFICE (DO/EO/US), CONCERNING A FILING UNDER 35 U.S.C. 371		
INTERNATIONAL APPLICATION NO. PCT/JP00/02474	INTERNATIONAL FILING DATE 17 April 2000 (17.04.00)	PRIORITY DATE CLAIMED 16 April 1999 (16.04.99)
TITLE OF INVENTION IMAGE PROCESSING APPARATUS AND MONITORING SYSTEM		
APPLICANT(S) FOR DO/EO/US OKAMOTO, Shusaku; NAKAGAWA, Masamichi; NOBORI, Kunio and MORIMURA, Atsushi		
Applicant herewith submits to the United States Designated/Elected Office (DO/EO/US) the following items and other information:		
1. <input checked="" type="checkbox"/> This is a <b>FIRST</b> submission of items concerning a filing under 35 U.S.C. 371. 2. <input type="checkbox"/> This is a <b>SECOND</b> or <b>SUBSEQUENT</b> submission of items concerning a filing under 35 U.S.C. 371. 3. <input checked="" type="checkbox"/> This is an express request to begin national examination procedures (35 U.S.C. 371(f)). The submission must include items (5), (6), (9) and (21) indicated below. 4. <input type="checkbox"/> The US has been elected by the expiration of 19 months from the priority date (Article 31). 5. <input checked="" type="checkbox"/> A copy of the International Application as filed (35 U.S.C. 371(c)(2)) a. <input type="checkbox"/> is attached hereto (required only if not communicated by the International Bureau). b. <input checked="" type="checkbox"/> has been communicated by the International Bureau. c. <input type="checkbox"/> is not required, as the application was filed in the United States Receiving Office (RO/US). 6. <input checked="" type="checkbox"/> An English language translation of the International Application as filed (35 U.S.C. 371(c)(2)). a. <input checked="" type="checkbox"/> is attached hereto. b. <input type="checkbox"/> has been previously submitted under 35 U.S.C. 154(d)(4). 7. <input checked="" type="checkbox"/> Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371(c)(3)) a. <input type="checkbox"/> are attached hereto (required only if not communicated by the International Bureau). b. <input type="checkbox"/> have been communicated by the International Bureau. c. <input type="checkbox"/> have not been made; however, the time limit for making such amendments has NOT expired. d. <input checked="" type="checkbox"/> have not been made and will not be made. 8. <input type="checkbox"/> An English language translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371 (c)(3)). 9. <input checked="" type="checkbox"/> An oath or declaration of the inventor(s) (35 U.S.C. 371(c)(4)). 10. <input type="checkbox"/> An English language translation of the annexes of the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371(c)(5)).		
<b>Items 11 to 20 below concern document(s) or information included:</b>		
11. <input checked="" type="checkbox"/> An Information Disclosure Statement under 37 CFR 1.97 and 1.98. 12. <input checked="" type="checkbox"/> An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.28 and 3.31 is included. 13. <input type="checkbox"/> A FIRST preliminary amendment. 14. <input type="checkbox"/> A SECOND or SUBSEQUENT preliminary amendment. 15. <input type="checkbox"/> A substitute specification. 16. <input type="checkbox"/> A change of power of attorney and/or address letter. 17. <input type="checkbox"/> A computer-readable form of the sequence listing in accordance with PCT Rule 13ter.2 and 35 U.S.C. 1.821 - 1.825. 18. <input type="checkbox"/> A second copy of the published international application under 35 U.S.C. 154(d)(4). 19. <input type="checkbox"/> A second copy of the English language translation of the international application under 35 U.S.C. 154(d)(4). 20. <input checked="" type="checkbox"/> Other items or information:		
47 sheets of drawing showing FIGS. 1-50, copy of English Translation of International Search Report, Form PTO-1449 and copies of the references cited therein (2 JP), and return receipt postcard		

U.S. APPLICATION NO. (PCT Article 17(2)(b))

09/807654

INTERNATIONAL APPLICATION NO  
PCT/JP00/02474

ATTORNEY'S DOCKET NUMBER  
5077-000031

**CALCULATIONS PTO USE ONLY**

21. ☒ The following fees are submitted:

**BASIC NATIONAL FEE (37 CFR 1.492 (a) (1) - (5)):**

Neither international preliminary examination fee (37 CFR 1.482)  
nor international search fee (37 CFR 1.445(a) (2)) paid to USPTO  
and International Search Report not prepared by the EPO or JPO ..... **\$1000.00**

International preliminary examination fee (37 CFR 1.482) not paid to  
USPTO but International Search Report prepared by the EPO or JPO ..... **\$860.00**

International preliminary examination fee (37 CFR 1.482) not paid to USPTO  
but international search fee (37 CFR 1.445(a)(2)) paid to USPTO ..... **\$710.00**

International preliminary examination fee (37 CFR 1.482) paid to USPTO  
but all claims did not satisfy provisions of PCT Article 33(1)-(4) ..... **\$690.00**

International preliminary examination fee (37 CFR 1.482) paid to USPTO  
and all claims satisfied provisions of PCT Article 33(1)-(4) ..... **\$100.00**

**ENTER APPROPRIATE BASIC FEE AMOUNT =**

\$ 860.00

Surcharge of **\$130.00** for furnishing the oath or declaration later than  
months from the earliest claimed priority date (37 CFR 1.492(e)). ☐ 20 ☐ 30

\$ 0.00

CLAIMS	NUMBER FILED	NUMBER EXTRA	RATE
Total claims	29 -20 =	9	x <b>\$18.00</b>
Independent claims	10 -3 =	7	x <b>\$80.00</b>
MULTIPLE DEPENDENT CLAIM(S) (if applicable)			+ <b>\$270.00</b>

\$ 162.00  
\$ 560.00  
\$ 270.00

**TOTAL OF ABOVE CALCULATIONS =**

\$ 1,852.00

☐ Applicant claims small entity status. See 37 CFR 1.27. The fees indicated above  
are reduced by 1/2.

\$ 0.00

**SUBTOTAL =**

\$ 1,852.00

Processing fee of **\$130.00** for furnishing the English translation later than ☐ 20 ☐ 30  
months from the earliest claimed priority date (37 CFR 1.492(f)).

\$ 0.00

**TOTAL NATIONAL FEE =**

\$ 1,852.00

Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be  
accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31). **\$40.00** per property +

\$ 40.00

**TOTAL FEES ENCLOSED =**

\$ 1,892.00

Amount to be  
refunded:

charged:

a. ☒ A check in the amount of \$ 1,892.00 to cover the above fees is enclosed.

b. ☐ Please charge my Deposit Account No. \_\_\_\_\_ in the amount of \$ \_\_\_\_\_ to cover the above fees.  
A duplicate copy of this sheet is enclosed.

c. ☒ The Commissioner is hereby authorized to charge any additional fees which may be required, or credit any  
overpayment to Deposit Account No. 08-0750. A duplicate copy of this sheet is enclosed.

d. ☐ Fees are to be charged to a credit card. **WARNING:** Information on this form may become public. **Credit card  
information should not be included on this form.** Provide credit card information and authorization on PTO-2038.

**NOTE:** Where an appropriate time limit under 37 CFR 1.494 or 1.495 has not been met, a petition to revive (37 CFR  
1.137 (a) or (b)) must be filed and granted to restore the application to pending status.

SEND ALL CORRESPONDENCE TO:

Gregory A. Stobbs  
Harness, Dickey & Pierce, P.L.C.  
P. O. Box 828  
Bloomfield Hills, MI 48303  
US

SIGNATURE

Gregory A. Stobbs  
NAME

28,764

REGISTRATION NUMBER

Date: April 13, 2001



## DESCRIPTION

## IMAGE PROCESSING APPARATUS AND MONITORING SYSTEM

## 5 Technical Field

The present invention relates to an image processing technique for generating synthetic images with images captured by a plurality of cameras. In particular, the present invention relates to an effective technique for a  
10 monitoring system that can be utilized as an aid to confirm safety when driving a vehicle.

## Background Art

In conventional monitoring systems in general, one or a  
15 plurality of monitoring cameras capture an image of an object to be monitored, and the image is displayed on a monitor. In this case, generally, monitors are prepared in the number corresponding to the number of the cameras installed for monitoring.

20 For example, a conventional safety monitoring system for vehicles is as follows. A camera for capturing images is installed around the vehicle, and the images captured by the camera are displayed on a monitor installed near the driving seat. This system allows the driver to confirm safety of  
25 places of which safety confirmation is difficult with eyes or a mirror, such as an area behind the vehicle, through the monitor.

Japanese Patent Publication No. 2696516 discloses a structure that displays images on a divided monitoring screen, depending on the gear or the car speed. More specifically, when it is determined that the vehicle is in the halt state  
5 or in the low speed state, the monitoring screen is divided into three sections, and images captured by three cameras installed on the right side, the left side and in a lower portion of the vehicle are synthesized and reproduced. When it is determined that the vehicle is in the forward running  
10 state, the monitoring screen is divided into two sections, and images captured by two cameras installed on the right side and the left side of the vehicle are synthesized and reproduced.

Japanese Laid-Open Patent Publication No. 11-78692  
15 discloses a video presenting apparatus for vehicles having a structure in which precise videos for each encountered scene are synthesized and displayed. More specifically, camera images are transformed and synthesized depending on the driving state of the vehicle such as backward parking,  
20 forward parking, parallel parking or a state where the vehicle goes into an intersection with an obstructed view.

However, such conventional structures are not necessarily convenient systems for users such as drivers of vehicles.

25

#### **Disclosure of Invention**

It is an object of the present invention to provide an

improved image processing apparatus or an improved monitoring system in the convenience of users such as drivers of vehicles.

More specifically, an image processing apparatus of the present invention includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image viewed from a virtual point of view from these camera images, wherein the image processing part changes at least one selected from the position, the direction of the line of sight, and the focal length of the virtual point of view in accordance with a running state of the vehicle.

It is preferable that the image processing part changes at least one selected from the position of the virtual point of view, the direction of the line of sight, and the focal length in accordance with a running speed of the vehicle.

It is preferable that the image processing part changes at least one selected from the position, the direction of the line of sight, and the focal length of the virtual point of view, and controls capturing of an image outside a view range of the changed virtual point of view.

It is preferable that the image processing part controls the capturing of an image outside a view range of the changed virtual point of view by changing a model for image synthesis.

It is preferable that the image processing part changes at least one selected from the position, the direction of the

line of sight, and the focal length of the virtual point of view in accordance with a steering angle of the vehicle.

It is preferable that the image processing part changes at least one selected from the position, the direction of the  
5 line of sight, and the focal length of the virtual point of view in accordance with results of detection by an object detecting sensor that is provided in the vehicle.

It is preferable that the image processing part includes an original mapping table and generates a synthetic  
10 image using a mapping table that is cut out from the original mapping table, and the image processing part changes at least one selected from the position, the direction of the line of sight, and the focal length of the virtual point of view by changing the mapping table to be cut out from the original  
15 mapping table.

According to another aspect of the present invention, an image processing apparatus includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic  
20 image viewed from a virtual point of view from these camera images, wherein the image processing part controls capturing of an image outside a view range of the virtual point of view in accordance with a running state of the vehicle.

According to another aspect of the present invention, a  
25 monitoring system includes a plurality of cameras shooting surroundings of a vehicle; an image processing part for receiving images captured by the plurality of cameras to

generate a synthetic image viewed from a virtual point of view from these camera images; and a display part for displaying the synthetic image, wherein the image processing part changes at least one selected from the position, the  
5 direction of the line of sight, and the focal length of the virtual point of view in accordance with a running state of the vehicle.

More specifically, an image processing apparatus of the present invention includes an image processing part for  
10 receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing part generates an image including a first image and a second image as the synthetic image, the first image being viewed from a  
15 virtual point of view, the second image being viewed from a viewpoint that is different from the virtual point of view of the first image in at least one selected from the position, the direction of the line of sight and the focal length, or the second image being different from the first image in the  
20 model.

It is preferable that the second image is at least one of the camera images.

It is preferable that the first image is a close view image showing the vehicle and surroundings thereof, and the  
25 second image is a distant view image showing an area distant from the surrounding area of the vehicle that is shown by the close view image. It is preferable that the image processing



part arranges the distant view image around the close view image in the synthetic image. It is preferable that the distant view image is an image having continuity with the close view image.

- 5           It is preferable that the first image shows at least a part of the vehicle and at least a part of the surroundings of the vehicle, and the second image is obtained by enlarging at least a part of the area shown by the first image.

          According to another aspect of the present invention, a  
10   monitoring system includes a plurality of cameras shooting surroundings of a vehicle; an image processing part for receiving images captured by the plurality of cameras to generate a synthetic image from these camera images; and a display part for displaying the synthetic image, wherein the  
15   image processing part generates an image including a first image and a second image as the synthetic image, the first image being viewed from a virtual point of view, the second image being viewed from a viewpoint that is different from the virtual point of view of the first image in at least one  
20   selected from the position, the direction of the line of sight and the focal length, or the second image being different from the first image in the model.

          More specifically, an image processing apparatus of the present invention includes an image processing part for  
25   receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein in the synthetic image, the

image processing part displays at least a part of a vehicle region where the vehicle is present, and an attention drawing region for drawing attention in which at least a part of the surroundings of the vehicle is shown.

5           It is preferable that the synthetic image is an image viewed from a virtual point of view that is set above the vehicle.

          It is preferable that the image processing part displays an illustration image or an actual image of the  
10 vehicle on the vehicle region.

          It is preferable that the attention drawing region includes at least a part of a blind spot region around the vehicle that is not shot by any of the cameras. Alternatively, it is preferable that the attention drawing  
15 region corresponds to the blind spot region around the vehicle that is not shot by any of the cameras. It is preferable that the image processing part determines a range of a region obtained by combining the blind spot region and the vehicle region, using region data showing a projection  
20 region of the vehicle in each camera image.

          According to another aspect of the present invention, a monitoring system includes a plurality of cameras shooting surroundings of a vehicle; an image processing part for receiving images captured by the plurality of cameras to  
25 generate a synthetic image from these camera images; and a display part for displaying the synthetic image, wherein in the synthetic image, the image processing part displays at

least a part of a vehicle region where the vehicle is present, and an attention drawing region for drawing attention in which at least a part of the surroundings of the vehicle is shown.

5 More specifically, an image processing apparatus of the present invention includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing part  
10 generates the synthetic image, using a mapping table including first mapping data describing a correspondence relationship between pixels of the synthetic image and pixels of the camera images, and second mapping data describing an identifier showing that a pixel of the synthetic image  
15 corresponds to pixel data other than the camera images.

It is preferable that the pixel data other than the camera images shows the vehicle or a blind spot region that is present in at least a part of the surroundings of the vehicle.

20 It is preferable that the image processing part stores a predetermined image other than the camera images, and with respect to the pixel of the synthetic image, the second mapping data describes coordinate values in the stored predetermined image corresponding to the pixel.

25 It is preferable that the second mapping data describes pixel data corresponding to the pixel of the synthetic image.

According to another aspect of the present invention,

an image processing apparatus includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing  
5 part uses mapping data describing a correspondence relationship between pixels of the synthetic image and a plurality of pixel data including one or both of pixel data of the camera images and pixel data other than the camera images, and describing the rate of necessity with respect to  
10 each of the pixel data, and weights each pixel data in accordance with the rate of necessity, thereby generating the pixel data of the pixels of the synthetic image.

According to another aspect of the present invention, an image processing apparatus includes an image processing  
15 part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing part includes an original mapping table, cuts out a mapping table describing a correspondence relationship between pixels  
20 of the synthetic image and pixels of the camera images, and generates the synthetic image, using the cut-out mapping table.

#### **Brief Description of Drawings**

25 Fig. 1 is a conceptual diagram of a monitoring system of the present invention.

Figs. 2(a) and 2(b) are views showing an example of

camera arrangement.

Fig. 3 is an example of images captured by the cameras of Figs. 2(a) and 2(b).

Fig. 4 is a view conceptually showing the relationship  
5 between a virtual point of view and actual cameras.

Fig. 5 is an example of a generated synthetic image.

Figs 6(a) to 6(e) are views showing an image synthesis operation using a mapping table.

Fig. 7 is an example of a structure of a monitoring  
10 system of an embodiment of the present invention.

Fig. 8 is a flowchart showing an operation of an image synthesis part of Fig. 7.

Fig. 9 is an example of a structure of a mapping table.

Fig. 10 is a flowchart showing the detail of the pixel  
15 synthesis step S14 of Fig. 8.

Fig. 11 is an example of mapping data that describe pixel data other than the camera images.

Fig. 12 is an example of a vertically downward view image utilizing images from eight cameras.

Fig. 13 is an example of a vertically downward view  
20 image utilizing images from four cameras.

Fig. 14 is an example of a vertically downward view image utilizing images from two cameras.

Fig. 15 is an example of an obliquely downward view  
25 image.

Fig. 16 is an example of a panorama image in forward panorama mode.

Fig. 17 is an example of a panorama image in backward panorama mode.

Fig. 18 is an example of a combination of an obliquely downward view image and a panorama image.

5        Figs. 19(a) to 19(f) show an example of synthetic images when the height of the virtual point of view is changed in accordance with the running state of the vehicle.

      Figs. 20(a) to 20(d) show an example of synthetic images when the direction of the line of sight of the virtual point of view is changed in accordance with the running state of the vehicle.

      Figs. 21(a) and 21(b) show an example of synthetic images when the direction of the line of sight of the virtual point of view is changed in accordance with the steering angle of the vehicle.

      Figs. 22(a) and 22(b) are views showing an example of image switching in accordance with output signals from an object detecting sensor.

      Fig. 23 is a view showing an example of image switching in accordance with output signals of an object detecting sensor.

      Fig. 24 shows views showing an example of image switching in accordance with output signals of an object detecting sensor.

25        Fig. 25 is an example of a structure of a monitoring system of an embodiment of the present invention.

      Figs. 26(a) to 26(d) are views showing cutting-out of a

mapping table for parallel displacement of an image.

Figs. 27(a) to 27(g) are views showing cutting-out of a mapping table for enlargement or contraction of an image.

Fig. 28 is a view showing cutting-out of a mapping  
5 table in the shape of a quadrangle other than a square.

Fig. 29 is an example of camera images.

Fig. 30 is an example of a synthetic image where camera images showing an obliquely backward view is attached on the right and the left of a downward view image.

10 Fig. 31 is an example displaying a downward view image in a narrow range and a downward view image in a wide range side by side.

Fig. 32 is an example where obliquely downward view images are attached around the downward view image.

15 Fig. 33 is an example where an image utilizing a quasi-cylindrical model is attached around the downward view image.

Fig. 34 is an example where panorama images are attached around the downward view image.

Fig. 35 is an example where obliquely downward view  
20 images are attached around the downward view image with blank portions at the four corners.

Fig. 36 is an example displaying an image showing the position of a virtual point of view together with a camera image.

25 Fig. 37 shows views showing an example of camera images and mask data showing projection regions of the vehicle.

Figs. 38(a) to 38(c) are views showing an example where

an image of the vehicle is superimposed.

Fig. 39 shows views showing an example of synthetic images when a projection of the vehicle is converted as it is.

Fig. 40 shows views showing a part of the mask data.

5 Fig. 41 is an example of a synthetic image showing a vehicle region and a blind spot region.

Fig. 42 is a diagram showing a procedure for generating mapping data for obtaining the blind spot region and attaching images of a vehicle.

10 Figs. 43(a) to 43(d) are diagrams showing the relationship between the mask data and the pixels of the synthetic images.

Figs 44(a) to 44(c) show an example of synthetic images when mapping data obtained as a result of the procedure of  
15 Fig. 42 are used.

Fig. 45 is a diagram showing a procedure for generating mapping data for designating an attention drawing region.

Figs. 46(a) to 46(c) show an example of synthetic images when mapping data obtained as a result of the  
20 procedure of Fig. 45 are used.

Fig. 47 is a diagram for illustrating geometric transformation.

Fig. 48 is a diagram for illustrating geometric transformation.

25 Fig. 49 is a diagram for illustrating geometric transformation.

Fig. 50 is a diagram for illustrating geometric



transformation.

### Best Mode for Carrying Out the Invention

Fig. 1 is a conceptual diagram of a monitoring system  
5 of the present invention. In the monitoring system of Fig. 1,  
an image processing part 2 receives a plurality of camera  
images output from an image capturing part 1, and synthesizes  
the images to generate a synthesis image viewed from a  
virtual point of view. This synthetic image is displayed by  
10 a displaying part 3 such as a liquid crystal display. The  
image processing part 2 constitutes an image processing  
apparatus of the present invention.

In the description herein, a monitoring system of the  
present invention is mounted on a vehicle to assist parking  
15 or the like.

Figs. 2(a) and 2(b) show an example of camera  
arrangement. Fig. 3 is an example of images captured by the  
cameras arranged in Figs. 2(a) and 2(b). As shown in Figs.  
2(a) to 2(b), five cameras are provided in the vicinity of  
20 the door mirror, in the vicinity of the rear pillar and on  
the rear trunk. The image processing part 2 generates a  
synthetic image from five camera images when viewed from a  
virtual point of view.

The virtual point of view can be set to be oriented to  
25 an arbitrary direction in an arbitrary position in a three-  
dimensional space as in the case of a camera arrangement in  
video generation of computer graphics. The parameters that

determine the virtual point of view are coordinates (X-axis, Y-axis, Z-axis) representing the position of the virtual point of view in a three-dimensional space, three angles representing the direction, namely, an azimuth (horizontal rotation), an elevation angle (gradient) and a twist (rotation about the optical axis), and a focal length defining the view range. The focal length is a distance between the virtual point of view and a projection plane on which a synthetic image is generated. When the focal length is small, an image with a wide angle is generated. When the focal length is large, a telescopic image is generated. In actual cameras, the focal length is often represented by a distance (mm) with respect to the size (35mm) of a film that is the projection plane. In this specification, since the size of a synthetic image is represented by pixels, the focal length is also represented by pixels.

An appropriate synthetic image can be generated by selecting the position, the direction and the focal length of the virtual point of view depending on the situation.

Fig. 4 is a view conceptually showing the relationship between a virtual point of view and actual cameras. In Fig. 4, the virtual point of view is set above the vehicle. Fig. 5 is an example of a generated synthetic image, which is an image showing the vehicle and the scene around the vehicle viewed from the virtual point of view shown in Fig. 4.

In this embodiment, the image processing part 2 uses a mapping table 4 to generate a synthetic image from a

plurality of camera images. Herein, a "mapping table" refers to a table that describes the correspondence relationship between pixels for a synthetic image and pixel data of each camera image. As described later, in the mapping table, a  
5 correspondence relationship between pixels for a synthetic image and pixel data other than the camera images can be described.

#### Principle of the mapping table

10 Hereinafter, an operation for generating a synthetic image from a plurality of camera images using the mapping table will be described.

Figs. 6(a) to 6(e) are views for illustrating the outline of this operation. Figs. 6(a) to 6(c) are images captured by three cameras (corresponding to camera 3, camera  
15 1 and camera 2 in Fig 2(a), respectively. Fig. 6(d) is a mapping table used for generating a synthetic image from the camera images of Figs. 6(a) to 6(c). The image processing part 2 generates a synthetic image shown in Fig. 6(e) from  
20 the three camera images of Figs. 6(a) to 6(c), based on information of the mapping table of Fig. 6(d).

The mapping table shown in Fig. 6(d) has mapping data about each pixel of the synthetic image shown in Fig. 6(e). Each mapping datum describes information about a pixel of a  
25 camera image by which the corresponding pixel of the synthetic image is generated.

"Generating a synthetic image" means to determine

values of all the pixels of the synthetic image. Herein, the image processing part 2 determines values of pixels of the synthetic images in the order of the raster sequentially from the upper left, and the operation will be described by taking  
5 an example of the case of determining a value of a pixel P1 in the middle of the raster.

First, mapping data MP1 corresponding to the pixel P1 of the synthetic image is referred to. In the mapping data MP1, the corresponding camera number and the coordinates of  
10 the corresponding pixel of the camera image. In this example, in the mapping data MP1, "1" is described as the camera number and "340" as the X coordinate and "121" as the Y coordinate are described.

The image processing part 2 refers to pixel data C1 of  
15 the coordinates (340, 121) of the image captured by the camera 1 shown in Fig. 6(b), according to the description of the mapping data MP1 so as to determine the value of the pixel P1 of a synthetic image. Herein, the simplest method for determination is to use the value C1 of the pixel data as  
20 the value of the pixel P1. The synthetic image as shown in Fig. 6(e) is generated by determining the value of each pixel of the synthetic image by the same method.

For example, the mapping data MP2 corresponding to the pixel P2 of the synthetic image shows the pixel data C2 of  
25 the image captured by the camera 2 shown in Fig. 6(c), and therefore the value of the pixel data C2 is assigned as the value of the pixel P2. Similarly, the mapping data MP3

corresponding to the pixel **P3** of the synthetic image shows the pixel data **C3** of the image captured by the camera **3** shown in Fig. **6(a)**, and therefore the value of the pixel data **C3** is assigned as the value of the pixel **P3**. In the mapping table  
5 of Fig. **6(d)**, a region **R1** corresponds to the camera **1**, and a region **R2** corresponds to the camera **2**, and a region **R3** corresponds to the camera **3**.

A region **R4** other than the three regions **R1** to **R3** corresponding to the cameras is not covered by the cameras,  
10 or a blind spot that is hidden by the vehicle so that no corresponding camera images are present. For example, a pixel **P4** of the synthetic image is a pixel of the region **R4**. In this case, as the camera number of the mapping data **MP4** corresponding to the pixel **P4**, a specific camera number ("-1" in this example) that indicates that there is no  
15 corresponding camera image is used. When the camera number is "-1", predetermined pixel data indicating that this is outside the camera coverage or a blind spot are set for the corresponding pixel **P4**. Herein, black is set as the  
20 predetermined pixel data.

In the example of Figs. **6(a)** to **6(e)**, the mapping table is constituted so that a synthetic image overlooking the surroundings of the vehicle from the virtual point of view above the vehicle can be generated. This kind of mapping  
25 table can be prepared using geometric transformation that utilizes a so-called road surface plane model as described later. Alternatively, the mapping table can be prepared in

the trial and error manner while watching the synthetic image.

In fact, the correspondence relationship between the synthetic image and the pixel data of the camera images can be set freely depending on the purpose. For example, an  
5 arbitrary region of the camera image can be enlarged or contracted to synthesize the region in a part of the camera image, or a plurality of camera images can be aligned and synthesized. Thus, an arbitrary synthetic image can be generated.

10 For any mapping tables for generating a synthetic image, the image processing part 2 only has to perform the steps of referring to mapping data, referring to the pixel data of the designated camera image, and setting a pixel value of the synthetic image with respect to each pixel of the synthetic  
15 image. Therefore, the processing amount thereof can be significantly smaller than in the case where image synthesis is performed by an operation for each image synthesis. Therefore, in this method, the processing amount is constant, regardless of the type of the synthetic image, and high speed  
20 processing can be achieved, so that this method is most advantageous when used for monitoring that is required to be completed real-time in a predetermined period of time or for driving aid.

25 (First example of an operation for generating a synthetic image)

Fig. 7 is a diagram showing an example of a structure

of a monitoring system of this embodiment. In Fig. 7, the image processing part 2 includes an image synthesizing part 200, a display pattern storing part 210 and a display pattern setting part 220. The displaying storing part 210 includes a mapping table storing part 211 for storing a plurality of mapping tables as described above. The display pattern setting part 220 selects one mapping table MPT in accordance with the display pattern of a synthetic image to be generated from the mapping tables stored in the mapping table storing part 211, and sets it to a mapping table reference part 202 of the image synthesizing part 200.

Furthermore, the display pattern storing part 210 includes an illustration storing part 212 for storing various illustration images. The display pattern setting part 220 reads out an illustration image necessary for generation of a synthetic image from the illustration image storing part 212, and sets the illustration image to an illustration reference part 203 of the image synthesizing part 200. Here, the illustration image showing the vehicle is set.

The image synthesizing part 200 generates a synthetic image using a camera image output from the image capturing part 1 in accordance with the mapping table MPT set in the mapping table reference part 202. A timing generating part 205 generates timing signals for generating an animation sequence of the synthetic image.

Each camera 101 is provided with a pair of frame memories 102a and 102b. Each camera 101 is of a CCD type in

this example. When the camera is of a CMOS type, the camera can be provided with a frame memory function. In this case, the frame memories can be omitted.

Fig. 8 is a flowchart showing an operation of the image synthesizing part 200 for generation of one frame of a synthetic image.

First, the image capturing part 1 switches between the frame memory 102a in which images captured by each camera 101 are written and the frame memory 102b referred to by the image synthesizing part 200, in accordance with the timing signal for frame start output from the timing generation part 205 (step S11). The two frame memories are provided in each camera 101 and switched in order to prevent the writing and the reference from interfering with each other, because the image synthesizing part 200 refers to pixel data of the camera image here and there in accordance with the mapping table MPT, regardless of the order of writing from the camera 101, as described later.

Next, the timing generating part 205 generates a timing signal for designating a pixel for synthesis processing to the mapping table reference 202 (step S12). The mapping table reference part 202 reads out mapping data corresponding to the designated pixel from the mapping table MPT and outputs the data to the pixel synthesizing part 201 (step S13).

The pixel synthesizing part 201 generates a value of the pixel of the designated image in accordance with the



content of the input mapping data, using the pixel data of each camera image stored in the frame memory 102, the pixel data of the illustration images stored in the illustration reference part 203 and the like, and outputs the value to a  
5 video signal generating part 204 (step S14). The processing of step S14 will be described later.

The video signal generating part 204 converts the input pixel value of the synthetic image to a video signal in accordance with the timing signal output from the timing  
10 generating part 205, and outputs the video signal to a displaying part 3 (step S15).

The image synthesizing part 200 executes the processing of steps S12 to S15 with respect to all the pixels of the frame (steps S16, S17). When processing for the final pixel  
15 of the frame is completed, the timing generating part 205 starts the processing for the next frame.

The same processing can be executed by field unit.

Fig. 9 is a diagram showing an example of the structure of the mapping table. The mapping table shown in Fig. 9 has  
20 four types of mapping data MP11 to MP14. The structure of each mapping data is basically the same as those shown in Fig. 6, except that the rate of necessity of the pixel value is described, in addition to the camera number and the x, y coordinates. Herein, "the rate of necessity" is represented  
25 by values from 0 to 1, and the larger the value is, the higher the necessity is.

The mapping data MP11 describes the correspondence

relationship between the pixel of the synthetic image and the pixel data of one camera image. In this case, the rate of necessity is "1". The mapping data **MP12** describes the correspondence relationship between the pixel of the synthetic image and the pixel data of a plurality of camera images. In this case, the pixel data of the camera image are weighted in accordance with the rate of necessity to generate the pixel value of the synthetic image.

The mapping data **MP13** is used to attach the pixel data of the illustration image to the pixel of the synthetic image. More specifically, the number that does not correspond to any actual cameras ("99" in this example) is assigned to the illustration reference part **203** as the camera number so that an illustration image stored in the illustration reference part **203** can be identified.

The mapping data **MP14** indicates that the pixel of the synthetic image is in a so-called blind spot region. More specifically, when generating the mapping table, as a result of calculating the coordinate values of the pixel of the camera image that is referred to for generation of the pixel of the synthetic image, when the pixel of the coordinate values represent, for example, the vehicle itself, the pixel of the synthetic image fall on a region obtained by combining the vehicle region and the blind spot region. The blind spot region is a region obtained by subtracting the vehicle region from the combined region. For this reason, the blind spot region can be represented by assigning values that do not

exist as the camera numbers or the x, y coordinates. In this example, "-1" is assigned as the camera number.

Fig. 10 is a flowchart showing the flow of the detailed process of the pixel synthesis step S14.

5 First, a value of the pixel for synthesis is initialized to "0" (step S21).

Next, the camera number, the x, y coordinates and the rate of necessity are read out from the mapping data corresponding to the pixel for synthesis (step S22).

10 In step S22, when the camera number that has been read out is an identification number "99" indicating an illustration image (that is, the case of the mapping data MP13), the procedure goes to step S24, where the pixel data of the designated x, y coordinates of the illustration image  
15 stored in the illustration reference part 203 are read out and stored. Then, the procedure goes to step S28. On the other hand, when the camera number is not "99", the procedure goes to step S25.

In step S25, when the camera number that has been read  
20 out is an identification number "-1" indicating a blind spot region (that is, the case of the mapping data MP14), the procedure goes to step S26, where the pixel data representing the blind spot region that has been previously set are stored. Then, the procedure goes to step S28. On the other hand,  
25 when the camera number is not "-1", the procedure goes to step S27.

In step S27, when the camera number is not "99" or "-1",

that is, when it is determined that the pixel for synthesis is not in a region on which an illustration image is attached nor the blind spot region, the camera number represents the number of an actual camera, so that the pixel data of the designated x, y coordinates are read out from the camera images stored in the frame memory 102 of the corresponding camera number.

In step S28, the stored pixel data are weighted in accordance with the rate of necessity and added to the pixel value of the synthetic image. With respect to all the camera numbers described in the mapping data, steps S22 to S28 are repeated (steps S29, S30). When the processing is completed with respect to all the camera numbers, the image synthesizing part 201 outputs the values of the pixels (step S31).

For example, in the case of the mapping data MP12 shown in Fig. 9, the pixel value of the synthetic image can be obtained by the following equation.

$$\begin{aligned} & \text{The pixel value of the synthetic image} = \\ & \text{(the pixel value of the coordinates (10,10) of the} \\ & \text{camera 2} \times 0.3 \\ & + \text{the pixel value of the coordinates (56,80) of the} \\ & \text{camera 3} \times 0.5) \\ & / (0.3 + 0.5) \end{aligned}$$

Herein, division by the sum of the degrees of necessity (0.3 + 0.5) is performed to normalize the pixel value.

The above-described operation easily can generate a

synthetic image obtained by combining a plurality of camera images or a synthetic image including an illustration image. Furthermore, a synthetic image obtained by displaying a semi-transparent illustration image on an actual image can be  
5 generated by weighting the camera image and the illustration image in accordance with the rate of necessity. Moreover, a synthetic image obtained by displaying semi-transparent illustration images can be generated by weighting the pixel data other than the camera image in accordance with the rate  
10 of necessity.

Furthermore, as the illustration image, illustration images other than illustrations or images of the vehicle, such as those having a fixed shape on a screen such as a scale or an index of images, can be used.

15 In the description of this example, the camera number ("99") for referring to the illustration images and the camera number ("-1") for indicating the blind spot region are set independently. However, if the images representing the blind spot region are stored in the illustration reference  
20 part 203, the same camera number ("99") can be used for referring to the illustration images and for indicating the blind spot. In this case, for example, it is possible to store the illustration images representing the vehicle in combination with the images representing the blind spot  
25 region in the illustration reference part 203.

Furthermore, when the display pattern is changed in response to the designation of the display mode, it is

sufficient for the display pattern setting part 220 to read out a mapping table corresponding to a new display pattern from the mapping table storing part 211, and to set it in the mapping table reference part 202. Alternatively, a plurality  
5 of mapping tables may be synthesized so that a new mapping table can be generated.

In this example, as the mapping data MP13 shown in Fig. 9, the X, Y coordinate values of the illustration reference part 203 are described to display the illustration image.  
10 However, the pixel data itself of the illustration image can be described in the mapping data instead.

Fig. 11 is an example of the mapping data in this case. In the mapping data MP15 of Fig. 11, when the camera number is "99", that is, an illustration image is displayed, the  
15 pixel data itself of the illustration image are stored in the form of the values of red (R), green (G) and blue (B) in the region where the x coordinate and the y coordinate are stored.

For example, if the X coordinate and the Y coordinate are represented with 16 bits, the size of the region is 32  
20 bits. On the other hand, if the image data of the illustration image are represented with 8 bits each for R, G and B, the data are constituted with 24 bits in total. 8 bits "0" are added as the upper bits to make it 32 bit data, and the data are stored in the coordinate region. In this  
25 case, in the step S24 of Fig. 10, the R, G and B values described in the mapping data MP15 are read out and stored, instead of referring to the illustration reference part 203.

In this case, the mapping table and the illustration image are combined, so that the illustration reference part 203 can be eliminated. Furthermore, since the R, G and B values are read out directly from the mapping data, instead of reading out the x, y coordinate values from the mapping data and then reading out the pixel data of the corresponding illustration image, one procedure of the process can be eliminated.

Furthermore, to display the illustration image of the vehicle, in general, a value 1.0 is often assigned as the rate of necessity. However, as in the example of Fig. 11, the rate of necessity of the illustration image is a value smaller than 1.0 and the illustration image is synthesized with another camera image so that a scale or an index can be displayed in a semi-transparent manner on the synthetic image.

#### <Example of basic synthetic image>

The mapping table can be classified roughly into two groups of a single map and a composite map. "Single map" refers to a map where camera images and images from a virtual point of view are correlated by the pixel level, using a predetermined space model (which will be described in detail later). "Composite map" will be described later.

The display mode of the image processing part 2 is determined by the type of the mapping table set in the image synthesizing part 200. This display mode can be switched manually or automatically.

A typical single map and an example of a synthetic image using the single map will be described below.

#### Vertical downward view (Figs. 12 to 14)

5           A road surface plane model is used as the space model. The position of the virtual point of view is above the vehicle, and the direction of the line of sight is directed straight downward. This example is characterized in that the distance can be perceived easily and this example can be used  
10 advantageously for parking (perpendicular or parallel parking) or the like. Fig. 12 shows an image utilizing images from eight cameras. Fig. 13 shows an image utilizing images from four cameras. Fig. 14 shows an image utilizing images from two cameras.

#### 15           Obliquely downward view (Fig. 15)

          A road surface plane model is used as the space model. The position of the virtual point of view is above the vehicle, and the direction of the line of sight is directed  
20 obliquely backward. The range of view can be changed freely by adjusting the angle of the line of sight. In this mode, the backward of the vehicle can be looked out extensively in the right position relationship. This mode can be used advantageously as a rear view monitor at regular running, or  
25 to confirm safety at a low speed back-up such as the start of an operation for parking. At a low speed running, the range of view or the direction can be switched depending on the



speed.

#### Panorama (Figs. 16 and 17)

A cylindrical model is used as the space model. Fig. 16 is a forward panorama mode. The position of the virtual point of view is at the front edge of the vehicle, and the direction of the line of sight is straight ahead. In this mode, the state of the forward of the running direction can be seen, so that this mode can be utilized as a blind corner view monitor. More specifically, when the vehicle goes into a large street from a narrow lane, this mode allows the state of the large street to be recognized at once.

Fig. 17 is a backward panorama mode. The position of the virtual point of view is at the rear edge of the vehicle, and the direction of the line of sight is straight backward. In this mode, the backward portion of the vehicle can be looked out extensively as a 180 degree-panorama image. This mode can be used as a rear view monitor at running (especially, at high speed running).

20

#### Obliquely downward view + panorama (Fig. 18)

A road surface plane model and a cylindrical model are used as the space models. More specifically, as shown in Fig. 18, an image of a place near the rear of the vehicle is displayed in the obliquely downward view mode using the road surface plane model, and an image of a place far from the rear of the vehicle is displayed in the panorama mode using

the cylindrical model. Thus, this mode can be used advantageously in applications both in the obliquely downward view mode and the panorama mode.

5 <Display automatic switching>

In the monitoring system of the present invention, more safe and comfortable driving can be supported by switching the mapping table described above in accordance with various driving scenes, as appropriated. Furthermore, in one driving  
10 operation, it is essential for the driver to switch the mapping table in accordance with the ever-changing circumstances of the surrounding of the vehicle.

In other words, at least one of the position, the direction of the line of sight and the focal length of the  
15 virtual point of view of the synthetic image is changed in accordance with the running state of the vehicle, so that the convenience for the driver can be improved.

Figs. 19(a) to 19(f) are views showing an example in which the height of the virtual point of view of the  
20 synthetic image is changed. In the images shown in Figs. 19(a) to 19(f), the height of the virtual point of view is increased in descending order, and the display region including the vehicle becomes gradually wider. In other words, zoom-up is realized by lowering the height of the  
25 virtual point of view, and zoom-down is realized by raising the height of the virtual point of view. Even if the focal length of the virtual point of view is changed, the synthetic

image can be changed in the same manner as in Figs. 19(a) to 19(f).

A first example of a trigger for switching the height of the virtual point of view can be a running speed of the vehicle. For example, the virtual point of view can be raised as the running speed of the vehicle is increased, so that a wider area can be displayed. On the other hand, the virtual point of view can be lowered as the running speed of the vehicle is reduced, so that a narrower area can be displayed. Alternatively, when the vehicle is provided with an object detecting sensor for measuring the distance between the vehicle and an obstacle, output signals from the object detecting sensor can be used as the trigger for switching. For example, the virtual point of view can be lowered as the distance between the vehicle and the detected obstacle is reduced, so that a narrower area can be displayed. On the other hand, the virtual point of view can be raised as the distance is increased, so that a wider area can be displayed. Furthermore, a switching switch may be provided so that the driver or another passenger can designate enlargement or contraction of the image via the switch.

Figs. 20(a) to 20(d) are views showing an example in which the direction of the line of sight of the virtual point of view of the synthetic image is changed. In the images shown in Figs. 20(a) to 20(d), the direction of the line of sight of the virtual point of view is changed gradually from oblique backward to vertical downward. With the change in

the direction of the line of sight, the model for generating the synthetic image is also changed. In other words, the region for the synthetic image of a quasi-cylindrical model is larger as the direction of the line of sight is inclined more obliquely, so that a farther place can be seen easily.

In Figs. 20(a) to 20(d), it can be said that with the change in the direction of the line of sight of the virtual point of view, capturing an image outside of the view range of the changed virtual point of view is controlled. In other words, using the quasi-cylindrical model, the image that is outside of the view range of the virtual point of view can be captured. Then, the presence or the absence of the capturing of the image that is outside of the view range of the virtual point of view, the size thereof, and the image capturing range are controlled in accordance with the running state of the vehicle.

An example of a trigger for switching the direction of the line of sight of the virtual point of view can be the running speed of the vehicle, input with a switch or the like, as in the case of switching the height of the virtual point of view. For example, when the running speed of the vehicle is low, the line of sight is oriented straight downward. As the running speed is increased, the direction of the line of sight is inclined so that more backward can be displayed.

Figs. 21(a) and 21(b) are views showing an example where the direction of the line of sight of the virtual point of view of the synthetic image is changed in accordance with

the steering angle of the vehicle. In the example of Figs. 21(a) and 21(b), the virtual point of view is rotated about the optical axis in accordance with the steering angle. Fig. 21(a) is a synthetic image when the gear is in reverse and  
5 the steering wheel is straight. In this case, the vehicle moves straight backward, and therefore the virtual point of view is set in such a manner that the vehicle in the synthetic image is straight, and the regions on the right and the left of the vehicle are equally displayed, so that the  
10 area behind the vehicle can be seen easily. On the other hand, Fig. 21(b) is a synthetic image when the gear is in back and the steering wheel is rotated left. In this case, the vehicle moves left backward, and therefore the virtual point of view is rotated about the optical axis so that the  
15 area to which the vehicle moves, that is, the right side, the right backward and the backward of the vehicle can be seen easily. Thus, safety is ensured further.

Figs. 22(a) and 22(b) are views showing an example of image switching in response to output signals from the object  
20 detecting sensor. Fig. 22(a) is a scene before the object detecting sensor detects an obstacle approaching the vehicle. When the object detecting sensor detects an obstacle approaching the vehicle, the image on the screen is switched to the image shown in Fig. 22(b). In other words, the image  
25 is enlarged on the display so that the distance between the vehicle and the detected obstacle is recognized more easily.

Thus, when the object detecting sensor detects an

obstacle, the image is displayed with enlargement / contraction / rotation, etc., that is effected step by step or continuously in accordance with the distance to the obstacle, so that the obstacle can draw the attention of the driver or the passenger. Furthermore, the position of the virtual point of view can be changed in accordance with the position in which the obstacle is located.

Furthermore, as shown in Fig. 23, the region in which the obstacle is located can be enlarged and displayed, and the region can be enclosed with a frame and displayed. Alternatively, the frame can be flashed, or the color inside the frame can be reversed. This ensures further that the attention of the driver or the passenger can be drawn. Display only with enclosure with a frame without enlarging the image makes it possible to draw the attention of the driver or the passenger. Furthermore, a warning sound can be produced together with the change in the screen display so that the presence of an obstacle can be informed of.

Fig. 24 shows another example of image switching in accordance with the results of detection of the object detecting sensor. In Fig. 24, when an obstacle is detected backward of the vehicle, the direction of the line of sight of the virtual point of view is changed from straight downward to slightly backward. This change makes it possible to watch the obstacle located backward of the vehicle more easily. Furthermore, the virtual point of view can be displaced in parallel so that the detected obstacle is in the

center of the synthetic image.

In Figs. 19 to 24, the synthetic images in the case where the virtual point of view is above the vehicle have been described. However, even if the virtual point of view is located in another position, the convenience of the driver can be improved by changing at least one of the position, the direction of the line of sight and the focal length of the virtual point of view in accordance with the running state of the vehicle. As other examples of the position of the virtual point of view, the position of the rear trunk or the position of the head of the driver can be used.

In Figs. 20(a) to 20(d), with change in the direction of the line of sight of the virtual point of view, capturing an image outside of the view range is controlled. However, with the change in the position or the focal length of the virtual point of view, capturing an image that is outside of the view range can be controlled. Furthermore, an image that is outside of the view range of the virtual point of view can be captured without using the models. Moreover, control of capturing an image that is outside of the view range of the virtual point of view may be only performed in accordance with the running state of the vehicle without changing the virtual point of view.

(Second example of an operation for generating a synthetic image)

Display image easily can be switched by changing the

mapping table to be used, as appropriate. However, in this case, to switch display image continuously, it is necessary to prepare a large number of mapping tables. For this reason, it is necessary to provide a storing part having a large  
5 storage capacity, which is unfavorable.

In this example, an original mapping table larger than a synthetic image is provided, and a mapping table that is cut out from this original mapping table is used to synthesize the synthetic image. In this case, continuous  
10 switching of display image easily can be realized by changing the mapping table to be cut out, as appropriate.

Fig. 25 is a diagram showing the configuration of a monitoring system of this example. This configuration is different from that shown in Fig. 7 in that based on the  
15 coordinates of the pixel of the synthetic image output from a timing generating part 205 and the region designation information of the mapping table set by a display pattern setting part 220A, a map region setting part 302 generates an element of the corresponding mapping table and outputs the  
20 element to a mapping table reference part 202. In the mapping table reference part 202, the original mapping table stored in an original mapping table storing part 301 included in the display pattern storing part 210A is set by the display pattern setting part 220A.

25 More specifically, in the first example described above, in the step S13 shown in Fig. 8, the mapping data in the same position as the pixel of the synthetic image to be output at



present that is set by the timing generating part 205 is read out. In this example, after setting the region of the mapping table to be utilized on the original mapping table, the mapping table corresponding to the pixel of the synthetic  
5 image is read out.

The method for reading out the mapping data in this example will be described below. Figs. 26(a) to 26(d) and Figs. 27(a) to 27(g) schematically show the relationship between the synthetic image and the original mapping table in  
10 this example. In the example of Figs. 26(a) to 26(d), parallel displacement of the synthetic image can be realized by fixing the size of the region to be cut out from the original table to the same size as that of the synthetic image and changing the offset value. In the example of Figs.  
15 27(a) to 27(d), enlargement and contraction of the synthetic image can be realized by changing the size of the region to be cut out from the original table and the read-out step of the element.

First, the case where parallel displacement of the  
20 synthetic image will be described with reference to Figs. 26(a) to 26(d).

The synthetic image shown in Fig. 26(a) has the size of a width of  $W\_DISP$  and a height of  $H\_DISP$ , and the original mapping table shown in Fig. 26(b) has the size of a width of  
25  $W\_MAP$  and a height of  $H\_MAP$ . The original mapping table in this example is a table for creating an image in which a wide range of the surrounding of the vehicle is overlooked from

the virtual point of view in the sky above the vehicle. In the first example described above, if the focal length is constant, this corresponds to enlargement of the size of a projection plane from (W\_DISP, H\_DISP) to (W\_MAP, H\_MAP) with  
5 a constant distance between the virtual point of view and the projection plane. The original mapping table can be constructed in this manner. By enlarging the projection plane, the original mapping table can contain information on a wider range of areas. Fig. 26(d) is an image obtained by  
10 replacing the elements of the mapping table by the corresponding camera images and the illustration images.

Next, the display pattern setting part 220A designates a region to be used as the mapping table for generating the synthetic image by an offset (off\_x, off\_y) from the origin  
15 (0, 0) on the original mapping table. A region MPT of a size of (W\_DISP, H\_DISP) with the point (off\_x, off\_y) as the start point is used as the mapping table for image synthesis. The mapping data at the position obtained by adding this offset (off\_x, off\_y) to the X, Y coordinates of the pixel obtained  
20 by raster scanning of the synthetic image is read out from the mapping table reference part 202 and is output to the image synthesizing part 201. The synthesis processing of the pixel is performed according to the flowchart of Fig. 10 as in the first example. Fig. 26(c) is a synthetic image  
25 obtained with the mapping table MPT shown in Fig. 26(b).

In the case where the coordinates added with the offset exceeds the range of the original mapping table, the pixel

synthesizing part 201 is notified and display is performed in such a manner that a predetermined color (e.g., black) is used as the value for the pixel so that the region can be recognized.

5           This example makes it possible to generate a synthetic image when the virtual point of view is displaced in parallel to the road surface without increasing the number of the mapping tables, in the case where the virtual point of view is positioned so that it overlooks vertically from the above  
10 of the vehicle to the road surface, and a road surface plane model is used. In other words, in the first example described above, each of the virtual points of view displaced in parallel needs a corresponding mapping table. However, in this example, one original mapping table is sufficient. For  
15 example, when displacing the virtual point of view for each pixel for smooth displacement of the point of view, in the first example, a large number of mapping tables corresponding to all the movement steps are required. However, in this example, moving the virtual point of view for each pixel can  
20 be realized simply by changing the start position (off\_x, off\_y) at which the mapping table is cut out in one wide range original mapping table. Moreover, in this example, for example, when changing the position of the virtual point of view by dialing or changing the position of the virtual point  
25 of view toward the direction of an obstacle in proportion to the magnitude of the output of the obstacle detecting sensor, the position of the virtual point of view can be changed in a

large number of steps, so that a synthetic image easily can be generated in accordance with the circumstances.

In this example, the virtual point of view is displaced in parallel in a large number of steps, so that there is no  
5 need of using a large number of mapping tables. Therefore, the memory for storing the mapping tables only has to have a capacity for storing one original mapping table. Furthermore, in the first example, it takes time to switch or set the mapping tables, whereas in this example, setting offset is  
10 only required. Thus, high speed processing can be achieved.

Next, the case where the synthetic image is enlarged or contracted in the same manner will be described with reference to Figs. 27(a) to 27(g).

In Figs. 27(a) to 27(g), the timing generating part 205  
15 is assumed to designate the coordinates (x, y) of a pixel P1 of a synthetic image shown in Fig. 27(a). The display pattern setting part 220A designates a read-out step (step\_x, step\_y) of an element as well as a start position (off\_x, off\_y) of a region. In this case, if the coordinates of the  
20 mapping data MD corresponding to the pixel P1 is (u, v), the coordinates (u, v) can be obtained by the following equation.

$$u = \text{step\_x} * x + \text{off\_x}$$

$$v = \text{step\_y} * y + \text{off\_y}$$

25 The synthetic image can be enlarged or contracted smoothly by changing the value of the read-out step (step\_x, step\_y). When the region of the mapping table that is cut out

from the original mapping table changes to MPT1, MPT2, MPT3, and MPT4 in accordance with the read-out step (step\_x, step\_y), the synthetic image is changed to the images shown in Figs. 27(d), 27(e), 27(f) and 27(g).

- 5           When the coordinates (u, v) exceed the range of the original mapping table, for example, a designated color is output in the same manner as in the case of the parallel displacement described above. Values other than integers can be used as the value of the read-out step (step\_x, step\_y).
- 10          In this case, the values of (u, v) as a result of calculation are converted to integers.

- According to the method for enlargement and contraction of this example, the same synthetic image as in the case where the range of view is enlarged or contracted by changing
- 15          the height or the focal length of the virtual point of view can be generated, when the virtual point of view is positioned so that it overlooks vertically from the above of the vehicle to the road surface, and a road surface plane model is used.

- 20          For example, when a part of the original image is enlarged for display in response to an instruction or of the driver or a sensor input, an enlarged image is not abruptly output, but the image is enlarged smoothly by using the method of this example. As a result, it is easily recognized
- 25          as to which part of the region of the original image the enlarged image corresponds to.

Furthermore, parallel displacement as well as

enlargement and contraction of an image can be realized by changing the offset value as well as changing the read-out step.

In general, there is no need of restricting the region of the mapping table to a square. In other words, the display pattern setting part 220A can designate the region of a mapping table by the coordinates of four vertices of a quadrangle.

In Fig. 28, the region of a mapping table has a shape of a convex quadrangle, and is designated by four points **n1**, **n2**, **n3**, and **n4**. In this case, the coordinates (u, v) of the mapping data **MD** corresponding to a pixel **P1** of the coordinates (x, y) of the synthetic image can be obtained in the following manner.

First, the coordinates of a point **na** that divides the line segment connecting vertices **n1** and **n2** in a ratio of (y / H\_DISP : 1 - y / H\_DISP) are obtained. Similarly, the coordinates of a point **nb** that divides the line segment connecting vertices **n3** and **n4** in a ratio of (y / H\_DISP : 1 - y / H\_DISP) are obtained. Then, when the coordinates of a point that divides the line segment connecting vertices **na** and **nb** in a ratio of (x / W\_DISP : 1 - x / W\_DISP) are obtained, they are the coordinates (u, v) of the corresponding mapping data **MD**.

This manner of designation makes it possible to designate regions of arbitrary mapping tables, including parallel displacement, enlargement, contraction and rotation.

According to the method of this example, a synthetic image that matches precisely with the change of the virtual point of view such as parallel displacement of the virtual point of view, enlargement and contraction of the range of view or rotation parallel to the road surface can be generated, when a road surface plane model is used, and the virtual point of view is positioned so that it overlooks vertically from the above of the vehicle to the road surface. When the model or the direction of the virtual point of view is different, it is not necessarily possible to generate a synthetic image that matches precisely with the change of the virtual point of view. However, in this case as well, it is possible to generate a synthetic image approximate to the change of the virtual point of view, so that this method is significantly advantageous.

#### <A plurality types of image display>

The convenience of the driver can be improved by displaying a plurality of types of synthetic images on one screen, or displaying synthetic images and camera images on one screen at the same time. For example, the driver can recognize precisely the circumstances surrounding the vehicle without switching the screen display by displaying a place near the vehicle and a place far from the vehicle at the same time; displaying images in different directions at the same time; or displaying the entire body of the vehicle and a part of the enlarged vehicle at the same time.

Such display of a plurality of types of images easily can be realized with a composite map. A "composite map" refers to a mapping table obtained by cutting out necessary portions in the single map for appropriate transformation, attaching the cut-outs, or attaching camera images to the single map. The image display described below can be realized easily with a composite map. However, with respect to image display other than that, composite maps corresponding to various driving scenes can be created by combining at least two single maps, or a single map and a camera image.

Herein, an example of displaying an image including a downward view image viewed from the virtual point of view set above the vehicle as a close view image showing the vehicle and the surroundings thereof, using a road surface plane model, and a distant view image showing areas farther than the surrounding areas of the vehicle showing this downward view image will be described. Fig. 29 shows camera images that constitute the base of the description herein.

Fig. 30 is an example where camera images showing oblique backward as second images are attached on the right and the left of the downward view image as the first image. In this example, the point of view of the second image is different from the virtual point of view of the first image in the position, the direction of the line of sight and the focal length. In the image of Fig. 30, the image of a camera 2 shooting the scenery obliquely backward on the right is



arranged on the right side of the downward view image with left-right reversal. The image of a camera 6 shooting the scenery obliquely backward on the left is arranged on the left side of the downward view image with left-right reversal.

5 In other words, the images of cameras 2 and 6 installed in the vicinity of the right and left door mirrors are arranged with left-right reversal so that the images are displayed as if they were seen on the door mirrors. Therefore, the driver can grasp the circumstances surrounding the vehicle  
10 intuitively with the same sense as looking at the door mirror. The images can be displayed without left-right reversal.

Fig. 31 is an example where a downward view image showing a narrow range as the first image and a downward view  
15 image showing a wide range as the second image are displayed side by side. In this example, the virtual point of view of the second image is different from that of the first image in the height or the focal length. The image of Fig. 31 allows immediate grasp of both a place near the vehicle in detail  
20 and a wider range in the thumbnail manner.

Fig. 32 is an example where obliquely downward view images of the forward, the backward, the right, and the left of the vehicle as the second images are attached around the downward view image as the first image. In this example, the  
25 virtual point of view of the second image is different from that of the first image in the direction of the line of sight. Fig. 33 is an example where images that might be obtained

through a fisheye lens with a quasi-cylindrical model as the second images are attached around the downward view image as the first image. In this example, the second images are different from the first image in the model. Fig. 34 is an example where panorama images of the forward, the backward, the right, and the left of the vehicle as the second images are attached around the downward view image as the first image. In this example, the second images are different from the first image in the position of the virtual point of view and the model. The images of Figs. 32 to 34 allow the driver to grasp the distance with respect to the place near the vehicle and to look out extensively with respect to the place far from the vehicle.

It is not necessary to attach the distant view image on all the sides of the forward, backward, right and left of the downward view. A distant view image can be displayed only on the side that is desired to be seen, for example, only on the right side, or the backward.

As shown in Fig. 35, when the obliquely downward view images are attached around the downward view image on the forward, backward, right and left thereof, blank portions are provided at the four corners of the display region, so that no continuity of the obliquely downward view images can be emphasized.

When image display as shown in Figs. 32 to 35 is performed, display can be blurred by subjecting the surrounding distant images to filter processing. This allows

the driver to concentrate his/her attention on the surroundings of the vehicle. Furthermore, distortion in the surrounding distant images does not stand out.

Such partial blur processing is advantageous in the case of image display with a single map as well. For example, in the case of the downward view image as shown in Fig. 5, the same effect can be obtained by performing blur processing to the surrounding areas in which other parked vehicles are displayed without performing blur processing to the vehicle and the surroundings thereof. It is preferable to set an area within 10m from the vehicle as the region that is not subjected to blur processing. It is also possible to increase the intensity of blur with increasing the distance from the vehicle.

The image of Fig. 31 can be a synthetic image including a first image showing the surroundings of the vehicle and a second image obtained by enlarging at least a part of the region shown in the first image. The first image can show a part of the vehicle instead of the whole body of the vehicle, or can show a part of the surroundings of the vehicle.

Furthermore, the display screen can be a multiwindow display, and the synthetic image as described above, camera images, images showing the position of the virtual point of view, letter information or the like can be displayed in subwindows. This achieves easier grasp of the circumstances of the surroundings of the vehicle, and thus the convenience of the driver can be improved.

There may be many methods for display on a multiscreen. For example, as shown in Fig. 36, the image showing the position of the virtual point of view can be displayed on a subwindow together with a camera image or a synthetic image. 5 Thus, the position of the virtual point of view easily can be grasped.

Furthermore, for example, when an object detecting sensor detects an obstacle, a warning mark showing the position of the obstacle can be displayed on the camera image 10 or the synthetic image on each subwindow. In addition, the position of the obstacle can be displayed with letters on another subwindow.

<Display of a blind spot region and a region of the vehicle >

#### 15 Example 1

Fig. 37 is an example of mask data as region data indicating camera images and projection regions of the vehicle in the camera images. As shown in Fig. 37, the portion where the vehicle is projected in each camera image 20 is identified and mask data showing the identified projection region of the vehicle are previously stored in the image processing part 2. The black portion in the mask data shown in Fig. 37 is the projection region of the vehicle. The projection region of the vehicle previously can be determined 25 uniquely, if the specification and the directions of the cameras, and the shape of the vehicle are determined.

Fig. 38(a) is a vertically downward view image

synthesized with the camera images of Fig. 37. In the synthetic image shown in Fig. 38(a), the vehicle is projected white in the center of the image, which makes the image unclear.

5           Therefore, the mask data of each camera image are converted to the images viewed from the virtual point of view, and in the synthetic image, the projection region of the vehicle is blacked out. As a result, the image as shown in Fig. 38(b) can be obtained, which makes the image better.

10           In Fig. 38(a), the vehicle is projected in the center of the image, which makes the image unclear. In addition, an actual place in which the vehicle is located is unclear. This makes driving difficult. Therefore, the illustration image or the actual image of the vehicle is superimposed on  
15           the position on which the vehicle is actually located. For example, the image processing part 2 previously stores the illustration image or the actual image of the vehicle that is presupposed to be viewed from the standard virtual point of view, and this image is converted to an image viewed from the  
20           virtual point of view of the synthetic image to be displayed. Then, the converted image can be superimposed. As a result, the image shown in Fig. 38(c) can be obtained, and the size of the vehicle or the position relationship relative to the objects surrounding the vehicle can be recognized at once.  
25           Conversion of the image of the vehicle easily can be realized with the above-described mapping table.

          In this case, for example, the virtual point of view

provided above the vehicle, the virtual point of view positioned on the side, the virtual point of view provided forward or backward of the vehicle can be used as the standard virtual point of view. Furthermore, a plurality of  
5 standard virtual points of view can be provided and an image can be prepared with respect to each of the plurality of standard virtual points of view. When the position of the virtual point of view for generating the synthetic image is determined, the standard virtual point of view that provides  
10 the smallest distortion in the image during conversion of the image may be selected based on the position relationship of the virtual point of view and each standard virtual point of view.

Instead of attaching the illustration or the actual  
15 image of the vehicle, a three-dimensional model with a surface model or a solid model that are known in the field of CAD/CAM or CG can be attached to the synthetic image. Also in this case, images showing three-dimensional models viewed from the standard virtual point of view are previously  
20 prepared, and this image is converted to an image viewed from the virtual point of view of the synthetic image to be displayed. Then, the converted image can be superimposed. This conversion easily can be realized with the above-described mapping table.

25 Furthermore, as the image showing the region in which the vehicle is actually located, the synthetic image generated from the camera image itself may be utilized.

Furthermore, a part of the vehicle, for example, only the bumper portion may be displayed in the synthetic image, and for other portions, illustrations or actual images may be attached.

5

#### Example 2

The synthetic image viewed from the virtual point of view may include a region that does not belong to any camera coverage, and may include a region that cannot be captured by the camera because of interruption of the vehicle.

In order to solve this problem, in Example 1 described above, the synthetic image can be more clear by assigning predetermined pixel data to the projection region of the vehicle and blacking out the region.

In this example, as shown in Fig. 39, when the camera image on which the vehicle is shown is converted to an image from the virtual point of view without any additional processing, the converted image of the vehicle is included in the synthetic image, which make the image unclear (A1). In this case, the image can be clear by blacking out the region where the vehicle is shown.

However, in the image from the virtual point of view, a part of the vehicle may be shown in a portion where the vehicle does not exist (A2). In this case, it is not preferable to black out the portion of the vehicle in the image from the virtual point of view, because the portion that should be seen is also eliminated. This problem can

arise when the space model used for conversion of the original camera image to an image from the virtual point of view is different from that in the actual world that is shown on the camera (simplified in most cases). Therefore, in order to solve this problem with respect to its principle, it is necessary to calculate information on the depth of the actual world in realtime, which requires high speed operation ability in the apparatus. Therefore, it is difficult to carry this out.

10       Therefore, this problem can be solved by the following method.

Whether or not the pixel of the synthetic image is included in the projection region of the vehicle is determined by referring to the mask data that makes a pair with the original camera image. Generation of this pixel is switched depending on whether or not the pixel is included in the projection region of the vehicle. More specifically, the mask data is not converted to an image from the virtual point of view, but the mask data in the form of the original camera image is used.

Fig. 40 shows an example of the mask data. As shown in Fig. 40, mask data indicating a region that is not used for synthesis of an image from the virtual point of view such as the projection portion of the vehicle is provided with respect to each camera image.

In this case, for example, when the pixel data of a camera image for generation of a synthetic image is referred



to, mask data corresponding to this camera image is also referred to. When the pixel is included in the projection region of the vehicle, generation of the pixel is not performed, and a process such as assigning a specific color  
5 that can indicate that the region is a blind spot region can be performed.

As the mapping data MP14 described above, the mapping table itself can have information as to whether or not the pixel of a synthetic image is included in a blind spot region.  
10 In this case, in synthesis of an image from the virtual point of view, there is no need of referring to the mask data for every frame, so that high speed processing can be realized. Furthermore, this provides the advantage that there is no need of providing a storage part for storing the mask data.  
15 Fig. 41 shows an example of the results of image synthesis. In the synthetic image shown in Fig. 41, a vehicle region where the vehicle is located and a blind spot region around the vehicle are shown. Indicating the vehicle region makes it easy for the driver to grasp the position  
20 relationship or the distance between the vehicle and the circumstances of the surroundings. Furthermore, the area that is hardly seen directly from the driver's seat can be confirmed by the synthetic image. Moreover, indicating the blind spot region makes it possible for the driver to  
25 recognize the area that is not shot by any of the cameras, so that safety can be improved.

It is not necessary to indicate the entire vehicle

region where the vehicle is located, and a part of the vehicle region may be indicated. For example, when the number of cameras to be installed is limited so that only the vehicle or a part thereof can be captured, only the captured  
5 part of the vehicle region and the surrounding blind spot regions are indicated. Alternatively, when a specific part around the vehicle is enlarged for display, a part of the vehicle to be displayed and the surrounding blind spot region are indicated.

10 Furthermore, instead of the blind spot region, an attention drawing region for drawing the attention of the driver or the passengers of the vehicle may be indicated. This attention drawing region may be a region including a blind spot region around the vehicle that is not shot by any  
15 of the cameras, or may be a region corresponding to the blind spot region itself. The attention drawing region may be a region indicating a part of the surrounding of the vehicle.

The attention drawing region can be previously set by using the position relationship with the vehicle region,  
20 regardless of the camera shooting coverage. Therefore, synthesis can be performed by simple processing. When the attention drawing region includes the blind spot region, a portion captured by a camera that is not in a blind spot region can be hidden as the attention drawing region.  
25 However, for example, the attention drawing region can be made semi-transparent for display in combination with the blind spot region.

Fig. 42 is a diagram showing the procedure of generating mapping data in the case where the blind spot region is obtained with mask data, and illustration images are attached. In Fig. 42, <PT1> is a pixel of a synthetic image that is generated from one camera image. <PT2> is a pixel of a synthetic image for which two camera images are referred to, but one of the camera images is removed for projection of the vehicle, and the synthetic image is generated from the remaining one camera. <PT3> is a pixel of a synthetic image for which one camera image is referred to, and the camera image is removed for projection of the vehicle. <PT4> is a pixel of a synthetic image for which one camera image is referred to, but the camera image is removed for projection of the vehicle, and an illustration image of the vehicle is attached.

First, in a step 1, the reference coordinates and the rate of necessity are calculated. With respect to the pixels of the synthetic image, the reference coordinates are calculated, regarding all the camera images. This calculation is performed by geometric operation, which will be described later. In this case, when the obtained reference coordinates are outside the shooting coverage of the camera image (that is, a blind spot), (-1, -1) is described as the coordinates. Also here, the number of cameras that are referred to is obtained, and the inverse of that number is assigned as the rate of necessity. The rate of necessity can be assigned in another method or assigned by

manual input. In the step 1, the results show that <PT1> refers to camera 6, <PT2> refers to camera 4 and 5, <PT3> refers to camera 6, and <PT4> refers to camera 2.

Next, in a step 2, processing of the blind spot is performed by referring to the mask data indicating the projection region of the vehicle. In the mask data corresponding to cameras other than the camera whose coordinate values are (-1, -1), it is determined whether or not the point indicated by the coordinate value belongs to the projection region of the vehicle. When it belong to the projection region of the vehicle, the coordinate values are converted to (-1, -1). With this conversion, the value of the rate of necessity is calculated again when the number of cameras to be referred to is reduced.

With respect to <PT1>, a point (450, 200) in the mask data of the camera 6 does not belong to the projection region of the vehicle, as shown in Fig. 43(d), so that the coordinate values are not converted. With respect to <PT2>, a point (150, 280) in the mask data of the camera 4 belongs to the projection region of the vehicle, as shown in Fig. 43(b), so that the coordinate values of the camera 4 are converted to (-1, -1). On the other hand, a point (490, 280) in the mask data of the camera 5 does not belong to the projection region of the vehicle, as shown in Fig. 43(c), so that the coordinate values of the camera 5 are not converted. Then, the rate of necessity thereof is converted to "1". With respect to <PT3>, a point (110, 250) in the mask data of

the camera 6 belongs to the projection region of the vehicle, as shown in Fig. 43(d), so that the coordinate values of the camera 6 are converted to (-1, -1). With respect to <PT4>, a point (600, 290) in the mask data of the camera 2 belongs to the projection region of the vehicle, so that the coordinate values of the camera 4 are converted to (-1, -1).

Next, in a step 3, redundant data is organized to obtain the minimum necessary data for image synthesis. First, all the camera numbers having coordinate values of (-1, -1) are changed to "-1". Then, when all the camera numbers are "-1", these data are integrated to one (<PT3>, <PT4>). When camera numbers other than "-1" are present, data having a camera number of -1 are removed (<PT1>, <PT2>).

In a step 4, an illustration image of the vehicle is attached. With respect to the pixel of the synthetic image for attaching the illustration image of vehicle, the camera number of the mapping data is converted to "99", and the reference coordinates of the illustration image are set. In this example, <PT4> is the pixel for attaching the illustration image of vehicle, and therefore the camera number is converted to "99", and the coordinate values are converted to the reference coordinate values (360, 44) of the illustration image.

Fig. 44(a) is an example of a synthetic image in the case where the mapping data at the end of the step 1 is used. Fig. 44(b) is an example of a synthetic image in the case where the mapping data at the end of the step 3 is used. Fig.

44(c) is an example of a synthetic image in the case where the mapping data at the end of the step 4 is used.

Fig. 45 is a diagram showing a procedure of generating mapping data in the case where an attention drawing region is designated without using the mask data. In Fig. 45, <PT5> is a pixel in a synthetic image generated from one camera image. <PT6> is a pixel in a synthetic image on which an attention drawing region is designated. <PT7> is a pixel in a synthetic image on which an attention drawing region is designated, but an illustration image is attached.

First, in a step 1', an initial mapping table is generated. This is performed by the processing of the steps 1' and 3 shown in Fig. 42.

Next, in a step 2', an attention drawing region is designated. A synthetic image is created using the initial mapping table generated in the step 1', and an attention drawing region is designated in this synthetic image.

Next, in a step 3', the mapping data corresponding to the attention drawing region is rewritten. In the mapping data corresponding to the attention drawing region designated in the step 2', the camera number is converted to "-1" and the coordinates are converted to (-1, -1). Then, when the number of the cameras that are referred to is reduced, the value of the rate of necessity is calculated again.

Then, in a step 4', an illustration image of the vehicle is attached. In this example, since <PT7> is a pixel for attaching an illustration image, the camera number is

converted to "99" and the coordinate values are converted to the reference coordinates value (360, 44).

Fig. 46(a) is an example of a synthetic image in the case where the mapping data at the end of the step 1' is used.

5 Fig. 46(b) is an example of a synthetic image in the case where the mapping data at the end of the step 3' is used.

Fig. 46(c) is an example of a synthetic image in the case where the mapping data at the end of the step 4' is used.

In this manner, a process such as superimposing the  
10 image of the vehicle on the synthetic image, assigning a specific color to the entire blind spot region or the entire attention drawing region can be performed easily. When setting an attention drawing region, a predetermined attention drawing region is synthesized without referring to  
15 the mask data with respect to the cameras, so that a synthetic image can be generated more simply. On the other hand, when setting a blind spot region, the mask data with respect to the cameras are referred to, so that all the circumstances of the surroundings of the vehicle captured by  
20 the cameras can be reflected on the synthetic image.

In the above description, the monitoring system and the image processing apparatus of the present invention are applied to vehicles. However, the present invention also can be applied easily to movable bodies other than vehicles such  
25 as airplanes or ships. Moreover, the cameras can be installed in places to be monitored other than movable bodies, such as stores, houses, and showrooms.

The positions or the number of the plurality of cameras are not limited to those shown in this specification.

All or part of the functions of the image processing apparatus of the present invention may be realized with a  
5 dedicated hardware or may be realized with software. Moreover, recording media or transmission media storing programs for executing all or part of the functions of the image processing apparatus of the present invention on a computer can be utilized.

10

#### <Geometric transformation>

In order to create a mapping table for synthetic images, it is necessary to determine the coordinates of a pixel of each camera image corresponding to each pixel of a synthetic  
15 image viewed from a virtual point of view.

For this purpose, first, a world coordinate system ( $X_w$ ,  $Y_w$ ,  $Z_w$ ) corresponding to each pixel of a synthetic image from a virtual point of view is obtained. Then, the coordinates of pixels of a camera image corresponding to three-  
20 dimensional coordinates of the world coordinate system is obtained. This manner of using the two steps is convenient.

The ultimately required relationship is only a relationship between each pixel of a synthetic image from a virtual point of view and a pixel of each camera, and there  
25 is no reason for limiting to the mapping table obtained via the world coordinate system. However, the mapping table obtained via the world coordinate system clarifies the



significance of the synthetic image in the world coordinate system, which is a coordinate system in the actual world, so that this is important in that the synthetic image that easily can be correlated with the circumstances of the surroundings with the actual distance or the position relationship can be generated.

The world coordinates ( $X_w, Y_w, Z_w$ ) corresponding to the coordinates ( $V_x, V_y, V_z$ ) of the point of view of the synthetic image can be obtained by Equation (1):

$$\begin{pmatrix} X_w \\ Y_w \\ Z_w \end{pmatrix} = R_v \begin{pmatrix} V_x \\ V_y \\ V_z \end{pmatrix} + T_v$$

$$\text{where } R_v = \begin{pmatrix} r_{v11} & r_{v12} & r_{v13} \\ r_{v21} & r_{v22} & r_{v23} \\ r_{v31} & r_{v32} & r_{v33} \end{pmatrix}, \quad T_v = \begin{pmatrix} T_{xv} \\ T_{yv} \\ T_{zv} \end{pmatrix} \quad (1)$$

where as the parameters indicating the position and the direction of a virtual point of view, the coordinates in the world coordinate system of the point of view is represented by the position vector  $T_v = (T_{xv}, T_{yv}, T_{zv})$ , and the direction of the line of sight is indicated by a rotating matrix  $R_v$  having three rows and three columns indicating rotation to match the view plane coordinate system to the orientation of the world coordinate system.

Fig. 47 is a schematic view illustrating the relationship between the viewpoint coordinate system and the world coordinate system.

As shown in Fig. 48, the rotating matrix  $R_v$  is as follows:

$$R_v = \begin{bmatrix} \cos \alpha_v & 0 & -\sin \alpha_v \\ 0 & 1 & 0 \\ \sin \alpha_v & 0 & \cos \alpha_v \end{bmatrix} \begin{bmatrix} 1 & 0 & 0 \\ 0 & \cos \beta_v & -\sin \beta_v \\ 0 & \sin \beta_v & \cos \beta_v \end{bmatrix} \begin{bmatrix} \cos \gamma_v & \sin \gamma_v & 0 \\ -\sin \gamma_v & \cos \gamma_v & 0 \\ 0 & 0 & 1 \end{bmatrix} \quad (2)$$

where the angle of horizontal rotation (azimuth) of the line of sight with respect to the Y-Z plane of the world coordinate system is  $\alpha_v$ , the inclination angle (elevation angle) of the line of sight with respect to the X-Z plane is  $\beta_v$ , and the rotation (twist) around the optical axis of the camera is  $\gamma_v$ .

On the other hand, the relationship between the  $V_{xe}$  and  $V_{ye}$  of the viewpoint coordinate system ( $V_{xe}$ ,  $V_{ye}$ ,  $V_{ze}$ ) of the virtual point of view and the two-dimensional coordinate  $U_v$  and  $V_v$  on the projection plane can be represented by Equation (3) using the focal length  $f_v$  from perspective projection transformation.

$$\begin{aligned} u_v &= \frac{f_v}{V_{ze}} V_{xe} \\ v_v &= \frac{f_v}{V_{ze}} y_{ve} \end{aligned} \quad (3)$$

The focal length may be represented by the unit of mm or inch corresponding to the size, assuming that the projection plane is a film or a CCD, or may be represented by the pixels corresponding to the size of the synthetic image. In this example, the projection plane is normalized to have a

width of 2 and a height of 2 with the projection center as its center, and the focal length corresponding thereto is used.

Therefore, as for the relationship between the  
 5 coordinates on the projection plane and the pixels of the synthetic image, if the horizontal width of the image is  $W_v$  pixels, and the vertical width is  $H_v$  pixels, the coordinates  $(U_v, V_v)$  on the projection plane corresponding to the pixel positioned  $(S_v, T_v)$  from the upper right of the image can be  
 10 obtained by:

$$\begin{aligned} U_v &= 2 \times S_v / W_v - 1 \\ V_v &= 2 \times T_v / H_v - 1 \end{aligned} \quad (4)$$

As a result, the three-dimensional coordinates  $(X_w, Y_w,$   
 15  $Z_w)$  of the world coordinate system corresponding to an arbitrary pixel  $(S_v, T_v)$  of the synthetic image can be obtained from Equations (1) to (4), the position of the camera  $T_{xv}, T_{yv}, T_{zv}$ , the direction of the camera  $\alpha_v, \beta_v, \gamma_v$ , and the focal length  $f_v$  by Equation (5).

20

$$\begin{pmatrix} x_w \\ y_w \\ z_w \end{pmatrix} = R_v \begin{pmatrix} \frac{V_{ze}}{f_v} U_v \\ \frac{V_{ze}}{f_v} V_v \\ V_{ze} \end{pmatrix} + T_v = \begin{pmatrix} \left( \frac{2S_v - W_v}{f_v \cdot W_v} r_{v11} + \frac{2T_v - H_v}{f_v \cdot H_v} r_{v12} + r_{v13} \right) V_{ze} + T_{xv} \\ \left( \frac{2S_v - W_v}{f_v \cdot W_v} r_{v21} + \frac{2T_v - H_v}{f_v \cdot H_v} r_{v22} + r_{v23} \right) V_{ze} + T_{yv} \\ \left( \frac{2S_v - W_v}{f_v \cdot W_v} r_{v31} + \frac{2T_v - H_v}{f_v \cdot H_v} r_{v32} + r_{v33} \right) V_{ze} + T_{zv} \end{pmatrix} \quad (5)$$

However, in Equation (5), the depth  $V_{ze}$  corresponding to the coordinates  $(S_v, T_v)$  of the synthetic image is undetermined. In other words, it is necessary to determine

the depth value from each pixel to the object to be captured in the synthetic image.

If the three-dimensional shape of the object viewed from the virtual point of view can be known, the depth of each pixel can be obtained. However, this is difficult in general. Therefore, a model for the shape of the object viewed from the virtual point of view is assumed to obtain Vze, and the relationship between the coordinates of the synthetic image and the three-dimensional coordinates of the world coordinate system is obtained.

#### - Road surface plane model-

As one example thereof, the case where an object is on the road surface plane in contact with the vehicle will be described.

If it is assumed that all objects are present on a plane (road surface) of the world coordinate system, the three-dimensional coordinates (Xw, Yw, Zw) of the world coordinate system satisfies the following equation of a plane.

$$ax_w + by_w + cz_w + d = 0 \quad (6)$$

Therefore, Vze can be obtained by substituting Equation (6) in Equation (5) as follows.

$$V_{ze} = -f_v \frac{aT_{zv} + bT_{yv} + cT_{xv} + d}{aQ_1 + bQ_2 + cQ_3}$$

where  $Q_1 = r_{v11} \frac{2S_v - W_v}{W_v} + r_{v12} \frac{2T_v - H_v}{H_v} + r_{v13} f_v$

$$Q_2 = r_{v21} \frac{2S_v - W_v}{W_v} + r_{v22} \frac{2T_v - H_v}{H_v} + r_{v23} f_v$$

$$Q_3 = r_{v31} \frac{2S_v - W_v}{W_v} + r_{v32} \frac{2T_v - H_v}{H_v} + r_{v33} f_v \quad (7)$$

Therefore, from the coordinates (Sv, Tv) of the pixel  
 5 of the synthetic image from the virtual point of view, the  
 corresponding three-dimensional coordinates (Xw, Yw, Zw) of a  
 plane of the world coordinate system can be obtained by  
 substituting Equation (7) in Equation (5).

The coordinates of each pixel of each camera image  
 10 corresponding to the three-dimensional coordinate system (Xw,  
 Yw, Zw) in the world coordinate system can be obtained by  
 substituting the parameters of Tx, Ty, Tz, α, β, and γ  
 corresponding to the position and the direction of each  
 camera in the relative equation similar to Equation (1).

15 For example, if the position of the camera 1 is Tx1,  
 Ty1, and Tz1, and the direction thereof is α1, β1, and γ1,  
 the camera coordinate system Xel, Yel, and Zel of the camera  
 1 corresponding to the pixel (Sv, Tv) of the synthetic image  
 can be calculated with Equation (8).

20

$$\begin{bmatrix} X_{e1} \\ Y_{e1} \\ Z_{e1} \end{bmatrix} = R_1^{-1} \left( \begin{bmatrix} X_w \\ Y_w \\ Z_w \end{bmatrix} - \begin{bmatrix} T_{x1} \\ T_{y1} \\ T_{z1} \end{bmatrix} \right)$$

$$\text{where, } R_i^{-1} = \begin{bmatrix} \cos \gamma_i & -\sin \gamma_i & 0 \\ \sin \gamma_i & \cos \gamma_i & 0 \\ 0 & 0 & 1 \end{bmatrix} \begin{bmatrix} 1 & 0 & 0 \\ 0 & \cos \beta_i & \sin \beta_i \\ 0 & -\sin \beta_i & \cos \beta_i \end{bmatrix} \begin{bmatrix} \cos \alpha_i & 0 & \sin \alpha_i \\ 0 & 1 & 0 \\ -\sin \alpha_i & 0 & \cos \alpha_i \end{bmatrix} \quad (8)$$

The relationship between this camera coordinate system and the coordinate system (U1, V1) of the camera image can be calculated with Equation (3) as follows.

$$\begin{aligned} U1 &= f1 / Z1 \times X1 \\ V1 &= f1 / Z1 \times Y1 \end{aligned} \quad (9)$$

where the focal length of the camera 1 is f1. The pixel of the corresponding camera image can be calculated with Equation (10), assuming that the size of the camera image is H1 pixels in the vertical length and W1 pixels in the horizontal width, the aspect ratio is 1: 1, and the center of the camera is the center of the image.

$$\begin{aligned} S1 &= W1 / 2 \times (Uv + 1) \\ T1 &= H1 / 2 \times (Vv + 1) \end{aligned} \quad (10)$$

With the above procedure, the pixel (S1, T1) of the image of the camera 1 corresponding to the pixel (Sv, Tv) of the image from the virtual point of view can be obtained. The pixel coordinates (Sn, Tn) corresponding to (Sv, Tv) with respect to a general camera n other than the camera 1 can be calculated in the same manner. In the parameter table, the camera number n and its coordinates (Sn, Tn) are written by selecting one or a plurality of optimal coordinates among

them, depending on various conditions, for example, whether or not (Sn, Tn) is within the range of an actual camera image, or whether or not enlargement ratio or contraction ratio of the pixel is large or the like.

5

#### -Cylindrical model-

In the above-described road surface model, an object located above the horizon on a camera image is never on the plane of the road surface, even if the plane of the road surface is extended infinitely, so that the object cannot be viewed from the virtual point of view.

In order to reflect this object on the synthetic image from the virtual point of view, a cylindrical model as shown in Fig. 49 is used as a three-dimensional shape of the object.

15 This model is advantageous, for example, when the direction of the virtual point of view is nearly parallel to the road surface.

For simplicity, a cylindrical model having its axes in the X-axis and the Z-axis is used. This model is represented by Equation (11) with (Xc, Zc) as the center of an elliptic cylinder, using a parameter (a, c) of the ellipse. This also easily applies to models having their axes in the axes other than the X-axis and the Z-axis by rotation on the XZ plane.

25

$$\frac{(Xw - Xc)^2}{a^2} + \frac{(Zw - Zc)^2}{c^2} = 1 \quad (11)$$

The three-dimensional coordinates (Xw, Yw, Zw) of the

world coordinate system corresponding to the coordinates ( $S_v$ ,  $T_v$ ) of the synthetic image from the virtual point of view can be obtained by eliminating  $V_{ze}$  from Equation (5) using Equation (11). From these coordinates, as in the case of the  
5 road surface plane model, the pixel corresponding to each camera image is calculated, so that the relationship between the pixel ( $S_v$ ,  $T_v$ ) of the image from the virtual point of view and the pixel ( $S_n$ ,  $T_n$ ) of the camera image is obtained and the mapping table is created.

10 Furthermore, a combination of the road surface plane model and the cylindrical model is possible. First, the three-dimensional coordinates of the world coordinate are obtained with the road surface plane model. When the three-dimensional coordinates are outside the cylindrical model, or  
15 are not intersected with the plane, so that there is no solution, then the three-dimensional coordinates are obtained with the cylindrical model. Thus, synthesis can be performed in combination of the road surface plane model and the cylindrical model.

#### 20 -Quasi-cylindrical model-

In order to facilitate grasp of the circumstances in distant places in the periphery of the road surface plane model, a bowl-shaped quasi-cylindrical model is introduced in  
25 the periphery. Fig. 50 shows the shape of the model. The portion of a distant place is compressed for synthesis so that a wider range can be displayed. The shape of this



quasi-cylinder is represented by Equation (12).

$$\frac{(Xw - Xc)^2}{a^2} + \frac{(Yw - Yc)^2}{b^2} + \frac{(Zw - Zc)^2}{c^2} = 1 \quad (12)$$

The center of the bowl is  $(Xc, Yc, Zc)$ , and it has a  
5 length of  $(a, b, c)$  in the X-axis, the Y-axis and the Z-axis  
directions. As in the above cylindrical model, the three-  
dimensional coordinates  $(Xw, Yw, Zw)$  of the world coordinate  
system corresponding to the coordinates of the synthetic  
10 image from the virtual point of view are calculated, and the  
relationship between each pixel of the synthetic image and  
the pixel of each camera image can be obtained.

As in the case of the cylindrical model, a composite  
model in a combination with the road surface plane model can  
be used for synthesis.

15

-Processing for lens distortion correction-

Next, a method for correcting lens distortion by the  
mapping table will be described. When there is distortion  
due to lens distortion in actual camera images, the pixel  
20 coordinates corrected with respect to this distortion are  
calculated when an actual pixel  $(S1, T1)$  is obtained from  $Uv$   
and  $Vv$  as described above. Thus, the effect of lens  
distortion can be removed from the synthetic image. This  
distortion correction is incorporated into the relationship  
25 between the synthetic image  $(Sv, Tv)$  of the mapping table and  
the camera image  $(Sn, Tn)$ . Therefore, if the mapping table

corrected with respect to distortion is created first, at the actual synthesis, calculation for correction is not required. Also when distortion is not formalized, for example, in the case of the function of the distance from the lens center

5 that is used for conventional lens distortion correction, distortion correction can be achieved, provided that a pattern of lattice or the like is imaged and information on how each pixel moves because of lens distortion is obtained.

10

## CLAIMS

1. An image processing apparatus comprising:

an image processing part for receiving images captured  
5 by a plurality of cameras shooting surroundings of a vehicle  
to generate a synthetic image viewed from a virtual point of  
view from these camera images,

wherein the image processing part changes at least one  
selected from a position, a direction of a line of sight, and  
10 a focal length of the virtual point of view in accordance  
with a running state of the vehicle.

2. The image processing apparatus of claim 1,

wherein the image processing part changes at least one  
15 selected from a position, a direction of a line of sight, and  
a focal length of the virtual point of view in accordance  
with a running speed of the vehicle.

3. The image processing apparatus of claim 1,

wherein the image processing part changes at least one  
selected from a position, a direction of a line of sight, and  
a focal length of the virtual point of view, and controls  
capturing of an image outside a view range of the changed  
virtual point of view.

25

4. The image processing apparatus of claim 3,

wherein the image processing part controls the

capturing of an image outside a view range of the changed virtual point of view by changing a model for image synthesis.

5. The image processing apparatus of claim 1,

5        wherein the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal length of the virtual point of view in accordance with a steering angle of the vehicle.

10    6. The image processing apparatus of claim 1,

      wherein the vehicle includes an object detecting sensor for detecting an obstacle, and

      the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal  
15    length of the virtual point of view in accordance with results of detection by the object detecting sensor.

7. The image processing apparatus of claim 1,

      wherein the image processing part includes an original  
20    mapping table and generates a synthetic image using a mapping table that is cut out from the original mapping table, and

      the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal  
      length of the virtual point of view by changing the mapping  
25    table to be cut out from the original mapping table.

8. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image viewed from a virtual point of view from these camera images,

5            wherein the image processing part controls capturing of an image outside a view range of the virtual point of view in accordance with a running state of the vehicle.

9. A monitoring system comprising:

10           a plurality of cameras shooting surroundings of a vehicle;

an image processing part for receiving images captured by the plurality of cameras to generate a synthetic image viewed from a virtual point of view from these camera images;

15           and

a display part for displaying the synthetic image,

wherein the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal length of the virtual point of view in accordance  
20           with a running state of the vehicle.

10. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle  
25           to generate a synthetic image from these camera images,

wherein the image processing part generates an image including a first image and a second image as the synthetic

image,

the first image being viewed from the virtual point of view,

the second image being viewed from a viewpoint that is  
5 different from the virtual point of view of the first image  
in at least one selected from a position, a direction of a  
line of sight and a focal length, or

the second image being different from the first image  
in a model.

10

11. The image processing apparatus of claim 10,

wherein the second image is at least one of the camera  
images.

15

12. The image processing apparatus of claim 10,

wherein the first image is a close view image showing  
the vehicle and surroundings thereof, and

the second image is a distant view image showing an  
area distant from the surrounding area of the vehicle that is  
20 shown by the close view image.

13. The image processing apparatus of claim 12,

wherein the image processing part arranges the distant  
view image around the close view image in the synthetic image.

25

14. The image processing apparatus of claim 13,

wherein the distant view image is an image having

continuity with the close view image.

15. The image processing apparatus of claim 10, wherein  
the first image shows at least a part of the vehicle  
5 and at least a part of the surroundings of the vehicle, and  
the second image is obtained by enlarging at least a  
part of the region shown by the first image.

16. A monitoring system comprising:  
10 a plurality of cameras shooting surroundings of a  
vehicle;  
an image processing part for receiving images captured  
by the plurality of cameras to generate a synthetic image  
from these camera images; and  
15 a display part for displaying the synthetic image,  
wherein the image processing part generates an image  
including a first image and a second image as the synthetic  
image,  
the first image being viewed from a virtual point of  
20 view,  
the second image being viewed from a viewpoint that is  
different from the virtual point of view of the first image  
in at least one selected from a position, a direction of a  
line of sight and a focal length, or  
25 the second image being different from the first image  
in a model.

17. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images,

5 wherein in the synthetic image, the image processing part displays at least a part of a vehicle region where the vehicle is present, and an attention drawing region for drawing attention in which at least a part of the surroundings of the vehicle is shown.

10

18. The image processing apparatus of claim 17,

wherein the synthetic image is an image viewed from a virtual point of view that is set above the vehicle.

15 19. The image processing apparatus of claim 17,

wherein the image processing part displays an illustration image or an actual image of the vehicle on the vehicle region.

20 20. The image processing apparatus of claim 17,

wherein the attention drawing region includes at least a part of a blind spot region around the vehicle that is not shot by any of the cameras.

25 21. The image processing apparatus of claim 17,

wherein the attention drawing region corresponds to the blind spot region around the vehicle that is not shot by any



of the cameras.

22. The image processing apparatus of claim 20 or 21,

wherein the image processing part determines a range of  
5 a region obtained by combining the blind spot region and the  
vehicle region, using region data showing a projection region  
of the vehicle in each camera image.

23. A monitoring system comprising:

10 a plurality of cameras shooting surroundings of a  
vehicle;

an image processing part for receiving images captured  
by the plurality of cameras to generate a synthetic image  
from these camera images; and

15 a display part for displaying the synthetic image,

wherein in the synthetic image, the image processing  
part displays at least a part of a vehicle region where the  
vehicle is present, and an attention drawing region for  
drawing attention in which at least a part of the  
20 surroundings of the vehicle is shown.

24. An image processing apparatus comprising:

an image processing part for receiving images captured  
by a plurality of cameras shooting surroundings of a vehicle  
25 to generate a synthetic image from these camera images,

wherein the image processing part generates the  
synthetic image, using a mapping table including first

mapping data describing a correspondence relationship between pixels of the synthetic image and pixels of the camera images, and second mapping data describing an identifier showing that a pixel of the synthetic image corresponds to pixel data  
5 other than the camera images.

25. The image processing apparatus of claim 24,  
wherein the pixel data other than the camera images show the vehicle or a blind spot region that is present in at  
10 least a part of the surroundings of the vehicle.

26. The image processing apparatus of claim 24,  
wherein the image processing part stores a predetermined image other than the camera images, and  
15 with respect to the pixel of the synthetic image, the second mapping data describe coordinate values corresponding to the pixel in the stored predetermined image.

27. The image processing apparatus of claim 24,  
20 wherein the second mapping data describe pixel data corresponding to the pixel of the synthetic image.

28. An image processing apparatus comprising:  
an image processing part for receiving images captured  
25 by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images,  
wherein the image processing part uses mapping data

describing a correspondence relationship between pixels of the synthetic image and a plurality of pixel data including one or both of pixel data of the camera images and pixel data other than the camera images, and describing a rate of  
5 necessity with respect to each of the pixel data, and weights each pixel data in accordance with the rate of necessity,

thereby generating the pixel data of the pixels of the synthetic image.

10 29. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images,


wherein the image processing part includes an original  
15 mapping table, cuts out a mapping table describing a correspondence relationship between pixels of the synthetic image and pixels of the camera images, and generates the synthetic image, using the cut-out mapping table.

## ABSTRACT

A synthetic image viewed from a virtual point of view above a vehicle is generated, using images captured by a plurality of cameras shooting surroundings of the vehicle. In the synthetic image, an illustration image or an actual image of the vehicle is displayed in a vehicle region in which the vehicle is present. The area around the vehicle that is not shot by any of the cameras is displayed as a blind spot region.

1/47

FIG. 1



2/47

FIG. 2A





FIG. 2B



3/47

FIG. 3

Camera 1



Camera 3



Camera 2



Camera 5




Camera4



4/47


FIG. 4





5/47

FIG. 5



6/47






FIG. 7




8/47

FIG. 8




9/47

FIG. 9



10/47


FIG. 10





12/47

FIG. 12





13/47

FIG. 13






FIG. 14



14/47

FIG. 15



15/47

FIG. 16







FIG. 17




16/47

FIG. 18




17/47

FIG. 19A




Virtual point of view  
height : 2.75m

FIG. 19B




Virtual point of view  
height : 3m

FIG. 19C



Virtual point of view  
height : 3.25m

FIG. 19D




Virtual point of view  
height : 3.5m

FIG. 19E



Virtual point of view  
height : 3.75m

FIG. 19F




Virtual point of view  
height : 4m

Zoom-up  
Zoom-down

18/47


FIG. 20A



Orientation: 22° backward  
 (Model: Road surface plane +  
 quasi-cylindrical surface)



FIG. 20B



Orientation: 17° backward  
 (Model: Road surface plane +  
 quasi-cylindrical surface)




FIG. 20C



Orientation: 11° backward  
 (Model: Road surface plane +  
 quasi-cylindrical surface)



FIG. 20D




Orientation:  
 straight downward  
 (Model : road surface plane)




19/47

FIG. 21A



Region occupied by an automobile when the automobile is moved.

Virtual point of view




Region occupied by an automobile when the automobile is moved.

FIG. 21B

20/47


FIG. 22A



Object detecting  
sensor



FIG. 22B






21/47

FIG. 23


Region where an  
obstacle is present



09/807654

22/47

FIG. 24



23/47

FIG. 25




FIG. 26B

FIG. 26A





FIG. 26D

FIG. 26C



25/47

FIG. 27B




FIG. 27C




FIG. 27D

FIG. 27E


FIG. 27F

FIG. 27G




26/47

FIG. 28




27/47

FIG . 29



28/47

FIG. 30






29/47

FIG. 31

Downward view image in  
a narrow range

Downward view image in  
a wide range




30/47

# FIG. 32


Obliquely downward  
view image on the left

Obliquely Downward  
view image in front of  
the automobile

Obliquely Downward  
view image behind  
the automobile




Obliquely downward view image on the right



31/47

FIG. 33



5077-000031

32/47

FIG. 34






FIG . 35



09/807654


34/47

FIG. 36




1100  
1101  
1102  
1103  
1104  
1105  
1106  
1107  
1108  
1109  
1110  
1111  
1112  
1113  
1114  
1115  
1116  
1117  
1118  
1119  
1120  
1121  
1122  
1123  
1124  
1125  
1126  
1127  
1128  
1129  
1130  
1131  
1132  
1133  
1134  
1135  
1136  
1137  
1138  
1139  
1140  
1141  
1142  
1143  
1144  
1145  
1146  
1147  
1148  
1149  
1150  
1151  
1152  
1153  
1154  
1155  
1156  
1157  
1158  
1159  
1160  
1161  
1162  
1163  
1164  
1165  
1166  
1167  
1168  
1169  
1170  
1171  
1172  
1173  
1174  
1175  
1176  
1177  
1178  
1179  
1180  
1181  
1182  
1183  
1184  
1185  
1186  
1187  
1188  
1189  
1190  
1191  
1192  
1193  
1194  
1195  
1196  
1197  
1198  
1199  
1200  
1201  
1202  
1203  
1204  
1205  
1206  
1207  
1208  
1209  
1210  
1211  
1212  
1213  
1214  
1215  
1216  
1217  
1218  
1219  
1220  
1221  
1222  
1223  
1224  
1225  
1226  
1227  
1228  
1229  
1230  
1231  
1232  
1233  
1234  
1235  
1236  
1237  
1238  
1239  
1240  
1241  
1242  
1243  
1244  
1245  
1246  
1247  
1248  
1249  
1250  
1251  
1252  
1253  
1254  
1255  
1256  
1257  
1258  
1259  
1260  
1261  
1262  
1263  
1264  
1265  
1266  
1267  
1268  
1269  
1270  
1271  
1272  
1273  
1274  
1275  
1276  
1277  
1278  
1279  
1280  
1281  
1282  
1283  
1284  
1285  
1286  
1287  
1288  
1289  
1290  
1291  
1292  
1293  
1294  
1295  
1296  
1297  
1298  
1299  
1300  
1301  
1302  
1303  
1304  
1305  
1306  
1307  
1308  
1309  
1310  
1311  
1312  
1313  
1314  
1315  
1316  
1317  
1318  
1319  
1320  
1321  
1322  
1323  
1324  
1325  
1326  
1327  
1328  
1329  
1330  
1331  
1332  
1333  
1334  
1335  
1336  
1337  
1338  
1339  
1340  
1341  
1342  
1343  
1344  
1345  
1346  
1347  
1348  
1349  
1350  
1351  
1352  
1353  
1354  
1355  
1356  
1357  
1358  
1359  
1360  
1361  
1362  
1363  
1364  
1365  
1366  
1367  
1368  
1369  
1370  
1371  
1372  
1373  
1374  
1375  
1376  
1377  
1378  
1379  
1380  
1381  
1382  
1383  
1384  
1385  
1386  
1387  
1388  
1389  
1390  
1391  
1392  
1393  
1394  
1395  
1396  
1397  
1398  
1399  
1400  
1401  
1402  
1403  
1404  
1405  
1406  
1407  
1408  
1409  
1410  
1411  
1412  
1413  
1414  
1415  
1416  
1417  
1418  
1419  
1420  
1421  
1422  
1423  
1424  
1425  
1426  
1427  
1428  
1429  
1430  
1431  
1432  
1433  
1434  
1435  
1436  
1437  
1438  
1439  
1440  
1441  
1442  
1443  
1444  
1445  
1446  
1447  
1448  
1449  
1450  
1451  
1452  
1453  
1454  
1455  
1456  
1457  
1458  
1459  
1460  
1461  
1462  
1463  
1464  
1465  
1466  
1467  
1468  
1469  
1470  
1471  
1472  
1473  
1474  
1475  
1476  
1477  
1478  
1479  
1480  
1481  
1482  
1483  
1484  
1485  
1486  
1487  
1488  
1489  
1490  
1491  
1492  
1493  
1494  
1495  
1496  
1497  
1498  
1499  
1500  
1501  
1502  
1503  
1504  
1505  
1506  
1507  
1508  
1509  
1510  
1511  
1512  
1513  
1514  
1515  
1516  
1517  
1518  
1519  
1520  
1521  
1522  
1523  
1524  
1525  
1526  
1527  
1528  
1529  
1530  
1531  
1532  
1533  
1534  
1535  
1536  
1537  
1538  
1539  
1540  
1541  
1542  
1543  
1544  
1545  
1546  
1547  
1548  
1549  
1550  
1551  
1552  
1553  
1554  
1555  
1556  
1557  
1558  
1559  
1560  
1561  
1562  
1563  
1564  
1565  
1566  
1567  
1568  
1569  
1570  
1571  
1572  
1573  
1574  
1575  
1576  
1577  
1578  
1579  
1580  
1581  
1582  
1583  
1584  
1585  
1586  
1587  
1588  
1589  
1590  
1591  
1592  
1593  
1594  
1595  
1596  
1597  
1598  
1599  
1600  
1601  
1602  
1603  
1604  
1605  
1606  
1607  
1608  
1609  
1610  
1611  
1612  
1613  
1614  
1615  
1616  
1617  
1618  
1619  
1620  
1621  
1622  
1623  
1624  
1625  
1626  
1627  
1628  
1629  
1630  
1631  
1632  
1633  
1634  
1635  
1636  
1637  
1638  
1639  
1640  
1641  
1642  
1643  
1644  
1645  
1646  
1647  
1648  
1649  
1650  
1651  
1652  
1653  
1654  
1655  
1656  
1657  
1658  
1659  
1660  
1661  
1662  
1663  
1664  
1665  
1666  
1667  
1668  
1669  
1670  
1671  
1672  
1673  
1674  
1675  
1676  
1677  
1678  
1679  
1680  
1681  
1682  
1683  
1684  
1685  
1686  
1687  
1688  
1689  
1690  
1691  
1692  
1693  
1694  
1695  
1696  
1697  
1698  
1699  
1700  
1701  
1702  
1703  
1704  
1705  
1706  
1707  
1708  
1709  
1710  
1711  
1712  
1713  
1714  
1715  
1716  
1717  
1718  
1719  
1720  
1721  
1722  
1723  
1724  
1725  
1726  
1727  
1728  
1729  
1730  
1731  
1732  
1733  
1734  
1735  
1736  
1737  
1738  
1739  
1740  
1741  
1742  
1743  
1744  
1745  
1746  
1747  
1748  
1749  
1750  
1751  
1752  
1753  
1754  
1755  
1756  
1757  
1758  
1759  
1760  
1761  
1762  
1763  
1764  
1765  
1766  
1767  
1768  
1769  
1770  
1771  
1772  
1773  
1774  
1775  
1776  
1777  
1778  
1779  
1780  
1781  
1782  
1783  
1784  
1785  
1786  
1787  
1788  
1789  
1790  
1791  
1792  
1793  
1794  
1795  
1796  
1797  
1798  
1799  
1800  
1801  
1802  
1803  
1804  
1805  
1806  
1807  
1808  
1809  
1810  
1811  
1812  
1813  
1814  
1815  
1816  
1817  
1818  
1819  
1820  
1821  
1822  
1823  
1824  
1825  
1826  
1827  
1828  
1829  
1830  
1831  
1832  
1833  
1834  
1835  
1836  
1837  
1838  
1839  
1840  
1841  
1842  
1843  
1844  
1845  
1846  
1847  
1848  
1849  
1850  
1851  
1852  
1853  
1854  
1855  
1856  
1857  
1858  
1859  
1860  
1861  
1862  
1863  
1864  
1865  
1866  
1867  
1868  
1869  
1870  
1871  
1872  
1873  
1874  
1875  
1876  
1877  
1878  
1879  
1880  
1881  
1882  
1883  
1884  
1885  
1886  
1887  
1888  
1889  
1890  
1891  
1892  
1893  
1894  
1895  
1896  
1897  
1898  
1899  
1900  
1901  
1902  
1903  
1904  
1905  
1906  
1907  
1908  
1909  
1910  
1911  
1912  
1913  
1914  
1915  
1916  
1917  
1918  
1919  
1920  
1921  
1922  
1923  
1924  
1925  
1926  
1927  
1928  
1929  
1930  
1931  
1932  
1933  
1934  
1935  
1936  
1937  
1938  
1939  
1940  
1941  
1942  
1943  
1944  
1945  
1946  
1947  
1948  
1949  
1950  
1951  
1952  
1953  
1954  
1955  
1956  
1957  
1958  
1959  
1960  
1961  
1962  
1963  
1964  
1965  
1966  
1967  
1968  
1969  
1970  
1971  
1972  
1973  
1974  
1975  
1976  
1977  
1978  
1979  
1980  
1981  
1982  
1983  
1984  
1985  
1986  
1987  
1988  
1989  
1990  
1991  
1992  
1993  
1994  
1995  
1996  
1997  
1998  
1999  
2000  
2001  
2002  
2003  
2004  
2005  
2006  
2007  
2008  
2009  
2010  
2011  
2012  
2013  
2014  
2015  
2016  
2017  
2018  
2019  
2020  
2021  
2022  
2023  
2024  
2025  
2026  
2027  
2028  
2029  
2030  
2031  
2032  
2033  
2034  
2035  
2036  
2037  
2038  
2039  
2040  
2041  
2042  
2043  
2044  
2045  
2046  
2047  
2048  
2049  
2050  
2051  
2052  
2053  
2054  
2055  
2056  
2057  
2058  
2059  
2060  
2061  
2062  
2063  
2064  
2065  
2066  
2067  
2068  
2069  
2070  
2071  
2072  
2073  
2074  
2075  
2076  
2077  
2078  
2079  
2080  
2081  
2082  
2083  
2084  
2085  
2086  
2087  
2088  
2089  
2090  
2091  
2092  
2093  
2094  
2095  
2096  
2097  
2098  
2099  
2100  
2101  
2102  
2103  
2104  
2105  
2106  
2107  
2108  
2109  
2110  
2111  
2112  
2113  
2114  
2115  
2116  
2117  
2118  
2119  
2120  
2121  
2122  
2123  
2124  
2125  
2126  
2127  
2128  
2129  
2130  
2131  
2132  
2133  
2134  
2135  
2136  
2137  
2138  
2139  
2140  
2141  
2142  
2143  
2144  
2145  
2146  
2147  
2148  
2149  
2150  
2151  
2152  
2153  
2154  
2155  
2156  
2157  
2158  
2159  
2160  
2161  
2162  
2163  
2164  
2165  
2166  
2167  
2168  
2169  
2170  
2171  
2172  
2173  
2174  
2175  
2176  
2177  
2178  
2179  
2180  
2181  
2182  
2183  
2184  
2185  
2186  
2187  
2188  
2189  
2190  
2191  
2192  
2193  
2194  
2195  
2196  
2197  
2198  
2199  
2200  
2201  
2202  
2203  
2204  
2205  
2206  
2207  
2208  
2209  
2210  
2211  
2212  
2213  
2214  
2215  
2216  
2217  
2218  
2219  
2220  
2221  
2222  
2223  
2224  
2225  
2226  
2227  
2228  
2229  
2230  
2231  
2232  
2233  
2234  
2235  
2236  
2237  
2238  
2239  
2240  
2241  
2242  
2243  
2244  
2245  
2246  
2247  
2248  
2249  
2250  
2251  
2252  
2253  
2254  
2255  
2256  
2257  
2258  
2259  
2260  
2261  
2262  
2263  
2264  
2265  
2266  
2267  
2268  
2269  
2270  
2271  
2272  
2273  
2274  
2275  
2276  
2277  
2278  
2279  
2280  
2281  
2282  
2283  
2284  
2285  
2286  
2287  
2288  
2289  
2290  
2291  
2292  
2293  
2294  
2295  
2296  
2297  
2298  
2299  
2300  
2301  
2302  
2303  
2304  
2305  
2306  
2307  
2308  
2309  
2310  
2311  
2312  
2313  
2314  
2315  
2316  
2317  
2318  
2319  
2320  
2321  
2322  
2323  
2324  
2325  
2326  
2327  
2328  
2329  
2330  
2331  
2332  
2333  
2334  
2335  
2336  
2337  
2338  
2339  
2340  
2341  
2342  
2343  
2344  
2345  
2346  
2347  
2348  
2349  
2350  
2351  
2352  
2353  
2354  
2355  
2356  
2357  
2358  
2359  
2360  
2361  
2362  
2363  
2364  
2365  
2366  
2367  
2368  
2369  
2370  
2371  
2372  
2373  
2374  
2375  
2376  
2377  
2378  
2379  
2380  
2381  
2382  
2383  
2384  
2385  
2386  
2387  
2388  
2389  
2390  
2391  
2392  
2393  
2394  
2395  
2396  
2397  
2398  
2399  
2400  
2401  
2402  
2403  
2404  
2405  
2406  
2407  
2408  
2409  
2410  
2411  
2412  
2413  
2414  
2415  
2416  
2417  
2418  
2419  
2420  
2421  
2422  
2423  
2424  
2425  
2426  
2427  
2428  
2429  
2430  
2431  
2432  
2433  
2434  
2435  
2436  
2437  
2438  
2439  
2440  
2441  
2442  
2443  
2444  
2445  
2446  
2447  
2448  
2449  
2450  
2451  
2452  
2453  
2454  
2455  
2456  
2457  
2458  
2459  
2460  
2461  
2462  
2463  
2464  
2465  
2466  
2467  
2468  
2469  
2470  
2471  
2472  
2473  
2474  
2475  
2476  
2477  
2478  
2479  
2480  
2481  
2482  
2483  
2484  
2485  
2486  
2487  
2488  
2489  
2490  
2491  
2492  
2493  
2494  
2495  
2496  
2497  
2498  
2499  
2500  
2501  
2502  
2503  
2504  
2505  
2506  
2507  
2508  
2509  
2510  
2511  
2512  
2513  
2514  
2515  
2516  
2517  
2518  
2519  
2520  
2521  
2522  
2523  
2524  
2525  
2526  
2527  
2528  
2529  
2530  
2531  
2532  
2533  
2534  
2535  
2536  
2537  
2538  
2539  
2540  
2541  
2542  
2543  
2544  
2545  
2546  
2547  
2548  
2549  
2550  
2551  
2552  
2553  
2554  
2555  
2556  
2557  
2558  
2559  
2560  
2561  
2562  
2563  
2564  
2565  
2566  
2567  
2568  
2569  
2570  
2571  
2572  
2573  
2574  
2575  
2576  
2577  
2578  
2579  
2580  
2581  
2582  
2583  
2584  
2585  
2586  
2587  
2588  
2589  
2590  
2591  
2592  
2593  
2594  
2595  
2596  
2597  
2598  
2599  
2600  
2601  
2602  
2603  
2604  
2605  
2606  
2607  
2608  
2609  
2610  
2611  
2612  
2613  
2614  
2615  
2616  
2617  
2618  
2619  
2620  
2621  
2622  
2623  
2624  
2625  
2626  
2627  
2628  
2629  
2630  
2631  
2632  
2633  
2634  
2635  
2636  
2637  
2638  
2639  
2640  
2641  
2642  
2643  
2644  
2645  
2646  
2647  
2648  
2649  
2650  
2651  
2652  
2653  
2654  
2655  
2656  
2657  
2658  
2659  
2660  
2661  
2662  
2663  
2664  
2665  
2666  
2667  
2668  
2669  
2670  
2671  
2672  
2673  
2674  
2675  
2676  
2677  
2678  
2679  
2680  
2681  
2682  
2683  
2684  
2685  
2686  
2687  
2688  
2689  
2690  
2691  
2692  
2693  
2694  
2695  
2696  
2697  
2698  
2699  
2700  
2701  
2702  
2703  
2704  
2705  
2706  
2707  
2708  
2709  
2710  
2711  
2712  
2713  
2714  
2715  
2716  
2717  
2718  
2719  
2720  
2721  
2722  
2723  
2724  
2725  
2726  
2727  
2728  
2729  
2730  
2731  
2732  
2733  
2734  
2735  
2736  
2737  
2738  
2739  
2740  
2741  
2742  
2743  
2744  
2745  
2746  
2747  
2748  
2749  
2750  
2751  
2752  
2753  
2754  
2755  
2756  
2757  
2758  
2759  
2760  
2761  
2762  
2763  
2764  
2765  
2766  
2767  
2768  
2769  
2770  
2771  
2772  
2773  
2774  
2775  
2776  
2777  
2778  
2779  
2780  
2781  
2782  
2783  
2784  
2785  
2786  
2787  
2788  
2789  
2790  
2791  
2792  
2793  
2794  
2795  
2796  
2797  
2798  
2799  
2800  
2801  
2802  
2803  
2804  
2805  
2806  
2807  
2808  
2809  
2810  
2811  
2812  
2813  
2814  
2815  
2816  
2817  
2818  
2819  
2820  
2821  
2822  
2823  
2824  
2825  
2826  
2827  
2828  
2829  
2830  
2831  
2832  
2833  
2834  
2835  
2836  
2837  
2838  
2839  
2840  
2841  
2842  
2843  
2844  
2845  
2846  
2847  
2848  
2849  
2850  
2851  
2852  
2853  
2854  
2855  
2856  
2857  
2858  
2859  
2860  
2861  
2862  
2863  
2864  
2865  
2866  
2867  
2868  
2869  
2870  
2871  
2872  
2873  
2874  
2875  
2876  
2877  
2878  
2879  
2880  
2881  
2882  
2883  
2884  
2885  
2886  
2887  
2888  
2889  
2890  
2891  
2892  
2893  
2894  
2895  
2896  
2897  
2898  
2899  
2900  
2901  
2902  
2903  
2904  
2905  
2906  
2907  
2908  
2909  
2910  
2911  
2912  
2913  
2914  
2915  
2916  
2917  
2918  
2919  
2920  
2921  
2922  
2923  
2924  
2925  
2926  
2927  
2928  
2929  
2930  
2931  
2932  
2933  
2934  
2935  
2936  
2937  
2938  
2939  
2940  
2941  
2942  
2943  
2944  
2945  
2946  
2947  
2948  
2949  
2950  
2951  
2952  
2953  
2954  
2955  
2956  
2957  
2958  
2959  
2960  
2961  
2962  
2963  
2964  
2965  
2966  
2967  
2968  
2969  
2970  
2971  
2972  
2973  
2974  
2975  
2976  
2977  
2978  
2979  
2980  
2981  
2982  
2983  
2984  
2985  
2986  
2987  
2988  
2989  
2990  
2991  
2992  
2993  
2994  
2995  
2996  
2997  
2998  
2999  
3000  
3001  
3002  
3003  
3004  
3005  
3006  
3007  
3008  
3009  
3010  
3011  
3012  
3013  
3014  
3015  
3016  
3017  
3018  
3019  
3020  
3021  
3022  
3023  
3024  
3025  
3026  
3027  
3028  
3029  
3030  
3031  
3032  
3033  
3034  
3035  
3036  
3037  
3038  
3039  
3040  
3041  
3042  
3043  
3044  
3045  
3046  
3047  
3048  
3049  
3050  
3051  
3052  
3053  
3054  
3055  
3056  
3057  
3058  
3059  
3060  
3061  
3062  
3063  
3064  
3065  
3066  
3067  
3068  
3069  
3070  
3071  
3072  
3073  
3074  
3075  
3076  
3077  
3078  
3079  
3080

35/47  
 FIG. 37




36/47




Projection of the  
automobile of a user

FIG. 38A



Black the projection  
of the automobile

FIG. 38B



Superimpose an image  
of the automobile


FIG. 38C



37/47

FIG. 39

Camera 6



A1

Camera 4




A2



09/807654, 2/4/2004


38/47

FIG. 40



39/47

FIG. 41



<PT4>

Camera number	X coordinate	Y coordinate	Ratio of necessary
0	-1	-1	
1	-1	-1	
2	500	250	
3	-1	-1	
4	-1	-1	
5	-1	-1	
6	-1	-1	
7	-1	-1	

Camera number	x coordinate	y coordinate	Rate of necessity
0	-1	-1	
1	-1	-1	
2	-1	-1	
3	-1	-1	
4	-1	-1	
5	-1	-1	
6	-1	-1	
7	-1	-1	


Camera number	X coordinate	Y coordinate	Rate of necessity
-1	-1	-1	1

Camera number	x coordinate	y coordinate	Rate of necessity
90	360	44	1

41/47

FIG. 43A


Correspond to PT4 (660, 290)



Mask data of Camera 2

FIG. 43B

Correspond to PT2 (150, 280)



Mask data of Camera 4

FIG. 43C

Correspond to PT2 (480, 280)



Mask data of Camera 5

FIG. 43D

Correspond to PT1 (450, 200)

Correspond to PT3 (110, 250)



Mask data of Camera 6

42/47

FIG. 44A





FIG. 44B




FIG. 44C



43/47

FIG. 45



44/47

FIG. 46A




FIG. 46B

Attention  
drawing region




FIG. 46C






FIG. 47




FIG. 48




FIG. 49





FIG. 50



**Declaration and Power of Attorney for Patent Application  
(English Language Declaration)**

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name,

I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled

**IMAGE PROCESSING APPARATUS AND MONITORING SYSTEM**

the specification of which (check one)

☐ is attached hereto.

☒ was filed on **April 17, 2000** as United States Application No. or PCT International Application Number **PCT/JP00/02474** and was amended on \_\_\_\_\_ (if applicable).

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose to the United States Patent and Trademark Office all information known to me to be material to patentability as defined in Title 37, Code of Federal Regulations, Section 1.56.

I hereby claim foreign priority benefits under Title 35, United States Code, Section 119(a) - (d) or Section 365(b) of any foreign application(s) for patent or inventor's certificate, or Section 365(a) of any PCT International application which designed at least one country other than the United States, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's certificate or PCT International application having a filing date before that of the application on which priority is claimed.

**Prior Foreign Application(s)****Priority Not Claimed**

<u>11-109946</u> (Number)	<u>Japan</u> (Country)	<u>16/04/1999</u> (Day/Month/Year filed)
<u>                    </u> (Number)	<u>                    </u> (Country)	<u>                    </u> (Day/Month/Year filed)
<u>                    </u> (Number)	<u>                    </u> (Country)	<u>                    </u> (Day/Month/Year filed)

I hereby claim the benefit under 35 U.S.C. Section 119(e) of any United States provisional application(s) listed below:

\_\_\_\_\_  
(Application Serial Number)

\_\_\_\_\_  
(Filing Date)

\_\_\_\_\_  
(Application Serial Number)

\_\_\_\_\_  
(Filing Date)

\_\_\_\_\_  
(Application Serial Number)

\_\_\_\_\_  
(Filing Date)

I hereby claim the benefit under 35 U.S.C. Section 120 of any United States application(s), or Section 365(c) of any PCT International application designating the United States, listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States or PCT International application in the manner provided by the first paragraph of 35 U.S.C. Section 112, I acknowledge the duty to disclose to the United States Patent and Trademark Office all information known to me to be material to patentability as defined in Title 37, C.F.R., Section 1.56 which became available between the filing date of the prior application and the national or PCT International filing date of this application:

**Application Serial No.**

**Filing Date**

**Status – patented,  
pending, abandoned**

_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

POWER OF ATTORNEY: As a named inventor, I hereby appoint the following attorney(s) and/or agent(s) to prosecute this application and transact all business in the Patent and Trademark Office connected therewith. *(list name and registration number)*

Customer No. 27572

Harness, Dickey &amp; Pierce, P.L.C.



Send Correspondence to:

Direct Telephone Calls to: *(name and telephone number)*

Gregory A. Stobbs, Esq. (248) 641-1214

1-00  
Full name of sole or first inventor: Shusaku OKAMOTOInventor's signature: Shusaku OKAMOTODate: April 6, 2001Residence: Osaka, Japan JPXCitizenship: JapanesePost Office Address: 3-6-10-215, Hoshigaoka, Hirakata-shi, Osaka 573-0013, Japan2-00  
Full name of second joint inventor, if any: Masamichi NAKAGAWASecond Inventor's signature: Masamichi NakagawaDate: April 6, 2001Residence: Osaka, Japan JPXCitizenship: JapanesePost Office Address: 22-5-304, Fujisaka-kitamachi, Hirakata-shi, Osaka 573-0151, Japan

3-00

Full name of third joint inventor, if any: Kunio NOBORIThird Inventor's signature: Kunio NoboriDate: April 6, 2001Residence: Osaka, Japan JPXCitizenship: JapanesePost Office Address: 16-1-811, Joshoji-cho, Kadoma-shi, Osaka 571-0063, Japan

4-00

Full name of fourth joint inventor, if any: Atsushi MORIMURAFourth Inventor's signature: Atsushi MorimuraDate: April 6, 2001Residence: Nara, Japan JPXCitizenship: JapanesePost Office Address: 4-14-8, Nishitomigaoka, Nara-shi, Nara 631-0006, Japan

Full name of fifth joint inventor, if any: \_\_\_\_\_

Fifth Inventor's signature: \_\_\_\_\_

Date: \_\_\_\_\_

Residence: \_\_\_\_\_

Citizenship: \_\_\_\_\_